Procedure for Supplementary CMM Measurements for Quartz Block #3 — P0457

1 INTRODUCTION

- **1.1 Objective**. The objective of this procedure is to make supplemental coordinate measuring machine (CMM) measurements of Quartz Block #3 to complete the set of measurements needed to verify the SIA to Probe C interface.
- **1.2 Personnel**. The test director for this procedure is John Turneaure, responsible engineer for the Quartz Block (QB). The quality assurance (QA) and safety representative is Ben Taller. The CMM operator is Eric Lundahl of the Stanford Linear Accelerator Center (SLAC).
- **1.3 Flight Equipment Safety**. The quartz block is a program critical item. Damage to Quartz Block #3 that renders it unacceptable for flight use will cause a substantial program delay and a large cost impact. Quartz Block #3 shall be handled and transported only in the manner given in this procedure. Particular attention shall be given to preventing the quartz block from coming into contact with hard surfaces that could result in the quartz block being chipped. New handling processes shall be practiced with one of the plastic quartz block models to verify the handling process.
- **1.4 Redlining of Procedure**. This procedure shall be only redlined by the test director with concurrence by the QA representative.

2 TRANSPORT OF QUARTZ BLOCK TO SLAC

2.1 Packaging of Quartz Block. The quartz block shall be packed in its shipping container using the same materials used for shipping it from Speedring.

	Packaging verified:	Test Director	Date
		QA	Date
2.2 Installation into Transport Vehicle. The shipping container with the quartz block in it shall carried by two persons to the transport vehicle and strapped or tied into the floor of the transport vehicle so the shipping container does not slide or bounce during transport.			
	Installed as required:	Test Director	Date
		QA	Date
2.3 Transport . The test director shall drive the vehicle to SLAC taking precautions to strong breaking during the trip. The QA representative shall accompany the test director director shall be accompany the test director.		le to SLAC taking precautions to avoid bumps and ative shall accompany the test director on this trip.	
	No unusual events:	Test Director	Date

o unusual events:	Test Director	Date
	QA	Date

2.4 Removal from Transport Vehicle. The shipping container shall be inspected to verify that it has remained strapped or tied in position. The shipping container shall then be unstrapped or untied from the floor of the transport vehicle. After inspecting the route over which the shipping container will be carried, it shall be carried by two persons to the location of the CMM.

	Process completed:	Test Director	Date		
		QA	Date		
3	CALIBRATION STATU	S OF CMM			
	CMM Manufacturer, Mo	del & Serial No.:			
	Accuracy:				
	Calibration Date:				
		CMM Operator	Date		
		QA	Date		
4	MOUNTING OF QB IN	СММ			
4.1	Verify Handling and Mounting of QB in CMM . Using a plastic model of the quartz block, verify the handling and mounting of the quartz block in the CMM using the precautions given in section 1.3.				
	Verified:	Test Director	Date		
		QA	Date		
4.2	Mount QB in CMM. Mor process established in sect	ant the quartz block in t ion 3.1. Be sure to take	he CMM using the verified handling and mounting the precautions given in section 1.3.		
	Safely Completed:	CMM Operator	Date		
		QA	Date		
5	MEASUREMENTS & R	ESULTS			
5.1	Label CMM data as identify printout containing the rec to change the orientation of to section 4.	fied in this procedure an orded data to this proce f the quartz block for th	nd the attached Dwg #25768. Attach the CMM dure at the end of all measurements. If it is necessary ne various measurements, it shall be done according		

5.2 Establish Coordinate System

- **5.2.1** Use the 7 points in datum -C- given in Dwg #25768 (Sheet 2, Zone F6) to determine the direction of the +Z axis (outward normal of datum -C-) and the zero of the Z-axis.
- **5.2.2** Use datum -H- (Sheet 1, Zone E1) at the center of the 2.000 inch flange to establish its center in the X-Y plane (establishes zero positions of X- and Y-axes).
- 5.2.3 Use the outward normal of datum -D- (Sheet 1, Zone B6) to set the direction of the +X-axis.

5.3 Perform Measurements of Datum -G- and Report Results

- **5.3.1** Measure the 32 points labeled as G11 through G18, G21 through G28, G31 through G38, and G41 through G48 as described in Dwg #25768 (Sheet 2, Zone E2).
- **5.3.2** Record the 32 measurements in section 5.3.1 in Table 1.

Re	corded:	CMM Operator	Date
		QA	Date
5.3.3	Calculate and record th	e average Z-position of	of the above 32 points on datum -G
Av	erage Value (n.nnnn in	ch):	
		CMM Operator	Date
		QA	Date
5.3.4	Calculate and record th	e flatness tolerance zo	one using the 32 points on datum -G
Fla	ntness (n.nnnn inch) :		
		CMM Operator	Date
		QA	Date
5.3.5	Calculate and record th	e parallelism of the 32	2 points on datum -G- with respect to datum -C
Pa	rallelism (n.nnnn inch)	:	
		CMM Operator	Date
		QA	Date
5.3.6	Calculate and record th C- using G11 through (e rotation angles abou G18.	t the X- and Y-axes of -G1n- with respect to datum -
Ro	tation about X-axis:		
Ro	tation about Y-axis:		
		CMM Operator	Date
		QA	Date
5.3.7	Calculate and record th C- using G21 through (e rotation angles abou G28.	t the X- and Y-axes of -G2n- with respect to datum -
Ro	tation about X-axis:		
Ro	tation about Y-axis:		
		CMM Operator	Date
		QA	Date

5.3.8 Calculate and record the rotation angles about the X- and Y-axes of –G3n- with respect to datum - C- using G31 through G38.

R	otation about X-axis:			
R	otation about Y-axis:			
		CMM Operator	Date	
		QA	Date	
5.3.9 Calculate and record the rotation angles about the X- and Y-axes of –G4n- with respect to datum C- using G41 through G48.				
R	otation about X-axis:			
R	otation about Y-axis:			
		CMM Operator	Date	
		QA	Date	

Table 1

	Z Position (n.nnnn inch)						
G11		G21		G11		G21	
G12		G22		G12		G22	
G13		G23		G13		G23	
G14		G24		G14		G24	
G15		G25		G15		G25	
G16		G26		G16		G26	
G17		G27		G17		G27	
G18		G28		G18		G28	

5.4 Inspect 2.000 inch Dimension

5.4.1 Inspect 2.000 inch +0.020/-0.000 inch dimension in Dwg #25768 (Sheet 1, Zone B5) for each of the four flange ears associated with -G1-, -G2-, -G3- and -G4-. Record actual values for each ear in Table 2.

Passed:

CMM Operator	Date
--------------	------

QA _____ Date _____

Page 5

Table	2
-------	---

Flange Ear	Thickness (n.nnn inch)
G1	
G2	
G3	
G4	

5.5 Inspect 10.22 inch Dimension

5.5.1 Inspect 10.22 inch +0.04/- 0.02 inch dimension in Dwg #25768 (Sheet 1, Zone B5) in two places. Record actual values in Table 3.

Passed:	CMM Operator	_ Date
	QA	Date

Table 3

Location	Length (n.nnn inch)
+X Side	
-X Side	

5.6 Inspect 16.850 Max inch Dimension

5.6.1 Inspect 16.850 inch maximum dimension in Dwg #25768 (Sheet 1, Zone D5). Record actual value.

Recorded value (n.nnn inch):		
Passed:	CMM Operator	Date	e
	QA	Date	e

5.7 Inspect 9.3680 inch +/- 0.0005 inch Diameter

- 5.7.1 Perform diameter measurements on OD of flange (datum -H-) at four Z locations. With datum -Gat Z0, the four Z locations are Z1 = Z0 - 0.25 inch, Z2 = Z0 - 0.75 inch, Z3 = Z0 - 1.25 inch, and Z4 = Z0 - 1.75 inch. To establish the diameter at each Z location, make measurements at 20 angular locations; 5 equally spaced locations 9° 20 apart (centered on the flange holes) for each of the four flange sections.
- 5.7.2 Calculate average diameter and circularity for each Z location and record in Table 4 using the 20 measurements for each Z location.

	Z Location	Average Diameter (n.nnnn inch)	Circularity (n.nnnn inch)			
	Z1					
	Z2					
	Z3					
	Z4					
5.7.	3 Inspect 9.3680 inch +/- average diameter value	0.0005 inch dimension in D s in Table 4.	wg 25768 (Sheet 1, Zone F2) using the		
Passed:		CMM Operator	Date			
		QA	Date			
5.7.4	4 Calculate average diam	eter and cylindricity using a	ll 80 measurements. Record a	actual values.		
	Average diameter (n.nnnn	inch):				
	Cylindricity (n nnnn inch)	•				
	Cymariety (n.mini inch)	•				
		CMM Operator	Date			
		QA	Date			
5.8	Review Measurements for	Completeness				
5.8.	1 Review measurement d attached.	ata for completeness and co	nsistency, and verify that CM	IM data printout is		
	Done:	Test Director	Date			
		QA	Date			
6	TRANSPORT OF QUAR	FZ BLOCK TO HEPL				
6.1	Packaging of Quartz Block . The quartz block shall be packed in its shipping container using the same materials used for shipping it from Speedring.					
	Packaging verified:	Test Director	Date			
		QA	Date			
6.2	Installation into Transpor	t Vehicle. The shipping cont	ainer with the quartz block in	n it shall be		

Table 4

6.2 Installation into Transport Vehicle. The shipping container with the quartz block in it shall be carried by two persons to the transport vehicle and strapped or tied into the floor of the transport vehicle so the shipping container does not slide or bounce during transport.

two persons.

	Installed as required:	Test Director		Date
		QA		Date
6.3	3 Transport . The test director shall drive the vehicle to the Hansen Experimental Physics Lab (HEI taking precautions to avoid bumps and strong breaking during the trip. The QA representative sha accompany the test director on this trip.			
	No unusual events:	Test Director		Date
		QA		Date
6.4	Removal from Transport Vehicle . The shipping container shall be inspected to verify that it has remained strapped or tied in position. The shipping container shall then be unstrapped or untied from the floor of the transport vehicle. The shipping container shall be returned to flight stores carried by			

Process completed:	Test Director	Date
	QA	Date