

GRAVITY PROBE-B  
OPERATIONS ORDER FOR  
SCIENCE MISSION DEWAR

**VERIFICATION FDAS CABLE I7  
PROBE OUTPUT**

August 30, 1999

Originator D. Murray
-------------------------

Approvals:

Mike Taber  
Test Director

\_ Date \_\_\_\_\_

Dave Murray  
Test Director

\_ Date \_\_\_\_\_

Dorrene Ross  
Quality Engineer

Sasha Buchman  
Hardware Manager

\_\_\_\_\_ Date

**A SCOPE**

This procedure describes the steps to effect the verification of the GP-B FDAS (Facility Data Acquisition System) output for Probe Cable I7.

**B REFERENCE DOCUMENTS**

B.1 Procedures:

Procedure No. Title

None

B.2 Drawings

LMSC Drawing No. \_\_\_\_\_ Title \_\_\_\_\_

None

B.3 Figures

None

B.4 Supporting documentation

- a) GP-B Magnetic Control Plan, LMMS-5835031
- b) SMD Safety Compliance Assessment, LMMS GPB-100153C
- d) SM Dewar FMECA, LMMS GPB-100333
- e) FIST Emergency Procedures SU/GP-B P0141
- f) Probe/Dewar Hardware Kit List, SU/GP-B P0144
- g) SMD Final Assembly, LMMS 5833500

**C SAFETY**

C.1 In case of any injuries obtain medical treatment: at:

**LMMS Call 117      Stanford University Call 9-911**

C.2 Safety

The GP-B (FIST) Safety Plan, LMSC-F314447, discusses safety design, operating and maintenance requirements which the R&DD program office has adhered to. These requirements should be reviewed for applicability at any facility outside of R&DD (e.g. Stanford University) where FIST hardware is operated.

C.3 Hazards Analysis

The GP-B (FIST) Preliminary Hazards Analysis, LMSC-F314446, discusses hazards inherent in R&DD-developed FIST hardware in greater detail.

Operations Number  
Date Initiated  
Time Initiated

**D CONFIGURATION REQUIREMENTS:**

- a) SMD integrated with Probe. Liquid helium temperatures established in Probe.

**E HARDWARE REQUIRED:**

- a) FIST FDAS (Facility Data Acquisition System)

**F OPERATIONS:**

**1 Prepare FDAS for data collection:**

- 1.1 Verify Cable I-7 has been certified by simulated GRT/SDT/Heater inputs to FDAS per Operations Order 1167 .
- 1.2 Verify the FDAS is operational.
- 1.3 Set up scan list to acquire the following data set:  
Record FDAS program file name \_\_\_\_\_ .  
Record data file name \_\_\_\_\_ .
- 1.4 Verify connected, Cable I7 to FDAS BI7
- 1.5 Connect other end of Cable I7 to Probe at Connector J7.

**2 Data Scanning:**

- 2.1 Using AMonitor Data≅ function key verify output of FDAS, one channel at a time, is consistent with the data of Table 1.

**NOTE:**

**Heater voltage input is manually input from Power Supply Distribution Box.**

- 2.2 Verify temperature output of FDAS is consistent with other recorded temperatures (e.g., Cable I6 sensors).
- 2.3 Verify power output to heaters is consistent with precalculated values.

**Table 1 FDAS Data**

Item	Descriptor	Probe ID	FDAS CN	Heater P.S. Input - V	Heater <sup>1</sup> Resis - ohms	Calculated power - W	Measured power - W	Comment
<b>HEATERS</b>								
1	Cryo-pump /a	H10P	31	2.0	7970	0.00052		
2	Cryo-pump /b	H11P	32	2.0	8000	0.00050		
3	Plumbing /a	H12P	33	2.0	4018	.00096		
4	Plumbing /b	H13P	34	2.0	4019	.00096		
5	Window #1 /a	H16P	35	1.0	400 <sup>2</sup>	.0025		
6	Window #1 /b	H17P	36	1.0	400 <sup>2</sup>	.0025		
7	Window #2 /a	H18P	37	1.0	400 <sup>2</sup>	.0025		
8	Window #2 /b	H19P	38	1.0	400 <sup>2</sup>	.0025		
9	Window #3 /a	H20P	39	1.0	180 <sup>2</sup>	.0056		
10	Window #3 /b	H21P	40	1.0	180 <sup>2</sup>	.0056		
					2. These are not measured values			
					1. From ADP v.3 p.16			
<b>TEMP.                      SENSORS</b>								
				DAS Temp	Expected Temp Max/Min			Comments
5	Cryo-pump /a	{T15P}	127					
6	Cryo-pump /b	{T16P}	128					

**VERIFICATION FDAS CABLE I5 PROBE OUTPUT**

7	Plumbing /a SDT	[T17P]	151					
8	Plumbing /b SDT	[T18P]	152					
9	Window #1 /a SDT	[T21P]	153					
10	Window #1 /b SDT	[T22P]	154					
11	Window #2 /a SDT	[T23P]	155					
12	Window #2 /b SDT	[T24P]	156					
13	Window #3 /a SDT	[T25P]	157					
14	Window #3 /b SDT	[T26P]	158					
	Window #4 Interanl SDT	[T27P]	159					

**3 Facility DAS Data Set:**

- 3.1 Using configuration for Cable I7 on FDAS collect one set of data (with raw data) and attach to this procedure.

**4 Procedure completed.**

Completed by:  
Witnessed by:  
Date:  
Time: