GRAVITY PROBE B PROCEDURE FOR PAYLOAD VERIFICATION

(PTP) UV CABLE CONTINUITY CHECK

14 December, 2001

Prepared by: B. Clarke

Approvals:

Program Responsibility	Signature	Date
B. Clarke Charge Control REE		
R. Brumley Payload Technical Manager		
B. Bencze Payload Electronics Manager		
D. Ross GP-B Quality Assurance		

IOTES:
Level of QA required during performance of this procedure:
Stanford QA Representative
Government QA Representative
All redlines must be approved by QA

14 December, 2001

(PTP) UV Cable Continuity Check Procedure No. P0888 Rev. –

Page 2 of 23

Revision Record:

Rev	Rev Date	ECO#	Summary Description

Acronyms and Abbreviations:

Acronym / Abbreviation	Meaning

Table of Contents

A Scope	4
B Requirements Verification	
C Configuration Requirements	
D Hardware Required	
E Software Required	
F Procedures Required	
G Equipment Pretest Requirements	
H Personnel Requirements	
I Safety Requirements	
J General Instructions	
K References and Applicable Documents	
L Operations.	

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P*0888 Rev.* – Page 4 of 23

A Scope

This procedure is **an engineering test** to verify the optical continuity of the installed flight UV cable from the AFT ECU to the top hat optical LEMO connectors. The optical cables will have already been connected to the AFT ECU but not yet connected at the top hat. The UV lamps and switches (in the AFT ECU) will be operated and the resulting UV flux through the cable will be measured.

B Requirements Verification

This is and engineering test only. No requirements are verified using this procedure.

C Configuration Requirements

- C.1 The UV cables must be connected to the AFT ECU (SMA end of cable).
- C.2 The optical SMA connectors must be torqued but not staked.
- C.3 The UV cables must not be connected at the top hat (LEMO end).
- C.4 The LEMO end of the cables must be accessible.
- C.5 The spacecraft must be configured such that the UV lamps and switches may be operated using CSTOL commands.

D Hardware Required

D.1 Flight hardware required

Description	No. Req'd
GP-B spacecraft and payload	1
Fiber optic cables, P/N 8A00649-103, Rev A	3

D.2 Commercial test equipment

Manufacturer	Model	Serial Number	Calibr. Exp. Date
Keithly Autoranging Picoammeter	485		
HP 0-25 V Dual Channel DC Power Supply	E3620A		
Resonance Ltd. Cs-Te photodiode	Cs-Te M-D-L		

14 December, 2001

Procedure No. P*0888 Rev.* – Page 5 of 23

D.3 Mechanical/Electrical Special test equipment

Description	Part No.	Rev. no.	Serial No.	Certification Date
SMA to LEMO fiber optic jumper	N/A	N/A	N/A	N/A

D.4 Tools

Description	No. Req'd
5X optical visor	1
Fiber optic inspection microscope	1

D.5 Expendables

Description	Quantity
Reagent grade isopropyl alcohol	N/A, on hand.
Filtered compressed air	N/A, on hand.
Lint free wipes and swabs	N/A, on hand.
Filtered dry nitrogen gas (cylinder) to be used for purging the UV section of the ECU during lamp operation.	N/A, on hand

E Software Required

E.1 Flight Software

Flight Software Name	Version No.
N/A	

E.2 CSTOL Scripts

CSTOL Script Name		Version No.
N/A		

E.3 SPC Scripts

SPC Script Name	Version No.		
N/A			

E.4 Test Support Software

Test Software Name	Version No.
N/A	

14 December, 2001

(PTP) UV Cable Continuity Check Procedure No. P0888 Rev. –

Page 6 of 23

Procedures Required F

Procedure Name	Procedure No.
GP-B Maintenance and Testing at All Facilities	P0875
The following procedures and drawings are for reference only. They are	
not absolutely required in the performance of this procedure.	
Pre-Integration UV Fiber Optics checkout	P0429AB
Hook-up and Check-out of All Gyro Cables with Probe Connectors	P0431AB
UV Current Measurements in Probe C (RT)	P0435AB
(PTP) ECU Temporary Installation Including Cables GP-B Payload Verification	P0835 Rev NC
Test II Operations Order	
PROBE C CABLE CONNECTOR INTERFACE	LMMS drawing
	1C34103, Rev D

G **Equipment Pretest Requirements**

Equipment	Serial No.	Test Required	Proc. No.	Test F	Performed
	INO.			Date	Ву
N/A					

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P*0888 Rev.* – Page 7 of 23

H Personnel Requirements

H.1 Test Leader

The Test Leader shall be Bruce Clarke. He has overall responsibility for the implementation of this procedure.

H.2 Other Personnel

All personnel participating in this procedure shall work under the direction of the Test Leader who shall determine whether the person is qualified. Different people will likely be designated at different times. For this procedure, participating engineers are expected to be (at various times) Bill Bencze, Robert Brumley, Tom Welsh and Ned Calder.

The spacecraft POD shall be operated by a qualified POD operator assigned by Norm Bennet. Presently the approved POD operator is Thomas Wai.

The QA program office shall be notified prior to the start of this procedure. A Quality Assurance Representative designated by Dorrene Ross shall review any discrepancy noted during this procedure, and approve its disposition. The presently designated QA Representative is Russ Leese.

ONR shall be notified at least 24 hours prior to the start of this procedure.

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P*0888 Rev.* – Page 8 of 23

I Safety Requirements

I.1 General

Extreme care must be taken to avoid accidentally bumping the Probe or damaging the connectors. Connector savers or equivalent adapters shall be used to protect the connector pins from damage during the measurements. A properly grounded ESD wrist strap must be worn while mating to or demating from Probe connectors.

All mate/demates involving flight connectors shall be logged.

I.2 Fiber Optics

The fiber optic cables are very fragile. Use care when mating and demating fiber optic connectors as not to break the optical fiber or scratch the polished optical surface at the end of the connectors. All fiber optic connectors must be rinsed with ethanol, dried with filtered air and inspected using a 5X optical visor and/or a fiber optic inspection microscope prior to mating to ensure there is no contamination on the optical surfaces.

I.3 UV Lamps

Ozone is produced when running the UV lamps in an oxygen environment. The amount of ozone that can be produced by these UV lamps is potentially a mild hazard to both hardware and personnel. In order to mitigate ozone production, the UV section of the ECU should be purged with dry filtered nitrogen gas while the UV lamps are powered on.

J General Instructions

J.1 Redline Authority

Authority to redline this procedure is given solely to the Test Lead with mandatory concurrence form the QA representative. Approval by the Hardware Manager shall be required if experiment functionality may be affected. QA Program Engineering concurrence is required before final review/buyoff (on last page) of the completion of the activity described in this procedure.

J.2 Test Anomaly or Discrepancy

Any nonconformance or test anomaly will be recorded in a D-log or as a Discrepancy Report per Quality Plan P0108. Do not alter or break test configuration if a test failure occurs; notify quality assurance.

Upon completion of this procedure, the QA Program Engineer, D. Ross or R. Leese will certify his/her concurrence that the effort was performed and accomplished in accordance with the prescribed instructions by signing and dating in the designated place(s) in this document.

J.3 Test Exit and Re-test Authority

Only the following persons have the authority to exit/terminate this test or perform a retest:

Test Lead Bruce Clarke or his designated representative

14 December, 2001

(PTP) UV Cable Continuity Check Procedure No. P0888 Rev. –

Page 9 of 23

QA Russ Leese, Dorrene Ross or other designated representative of Stanford Quality Assurance.

Κ **References and Applicable Documents**

None.

14 December, 2001

(PTP) UV Cable Continuity Check Procedure No. P0888 Rev. –

Page 10 of 23

Test started.		Date:
		Time:
L	OPERATIONS	
L.1	ECU UV BASELINE OUTPUT MEASUREMENT	
	SECTION STARTED AT DATE	TIME
	SIGNED: TEST LEAD	
	SIGNED:QA REPRESENTATIVE	PRINT NAME:
L.1.1	Insure the optical surfaces of the SMA-LEMO fi with isopropyl alcohol on a lint free wipe and dry replace any plastic caps after cleaning the fiber	ying with compressed filtered air. Do not
L.1.2	All fiber optic connectors mating to the probe as must be inspected for particulate contamination the probe flight connectors in the appropriate lo	prior to mating. Log all mate/de-mates from
L.1.3	Do not remove the vent covers from the UV servent caps has a mounting screw with a through of this section. Begin a light flow of dry nitrogen push the end of the line over the appropriate sc purge should be running for at least 10 minutes time the purge was started below:	hole drilled in it to allow for nitrogen purging gas (1-2 sccm) through the purge line and rew on the ECU-UV section vent cap. The
	Started purge @	
L.1.4	The following set of monitors must be recorded These monitors must also be available real time record the bridge filename below.	
	<u>Item</u>	Mnemonic
	UV LAMP A UV output (intensity monitor) UV LAMP A current UV LAMP A Bulb temperature UV A base temperature UV LAMP B UV output (intensity monitor) UV LAMP B current UV LAMP B Bulb temperature UV B base temperature	DE_UVLampA_OUT CE_UVLampA_I TE_UVLampA_T2 TE_UV_BASE_SDTa DE_UVLampB_OUT CE_UVLampB_I TE_UVLampB_T2 TE_UV_BASE_SDTb
	Bridge filename:	

Procedure No. P0888 Rev. – Page 11 of 23

L.1.5	Dawar up	the telemetr	, an bath LIV	/ lamas
L. I.O	Power up	the telemetry	y on both u v	i anibs.

Action	CSTOL Command
UV Lamp-A +/- 15 V ON	Set ECU UvLamp15V with Ecu_Side 1,Switch_Mode on
UV Lamp-B +/- 15 V ON	Set ECU UvLamp15V with Ecu_Side 2,Switch_Mode on
Time:	

L.1.6 Once 10 minutes has passed since the start of the purge in step L.1.3, turn on the thermoelectric heater/cooler and the RF exciter on UV lamp A by commanding:

Action	CSTOL Command
UV Lamp-A + 5V ON	Set ECU UvLamp5V with Ecu_Side 1,Switch_Mode on
UV Lamp-A + 30V ON	Set ECU UvLamp30V with Ecu_Side 1,Switch_Mode on
Time:	

- L.1.7 Record the lamp telemetry in Table L.1.1 below.
- L.1.8 Allow the lamp to warm for 20 minutes or until the Test Lead has determined the lamp output is stable enough to perform a measurement. Record the lamp telemetry in Table L.1.1 below.

TABLE L.1.1 - Lamp Telemetry w/Lamp A On, Lamp B Off

Item	Mnemonic	initial value (step L.1.7) (counts)	warm value (step L.1.8) (counts)	final value (step L1.12) (counts)
UV LAMP A UV output (intensity monitor)	DE_UVLampA_OUT			
UV LAMP A current	CE_UVLampA_I			
UV LAMP A Bulb temperature	TE_UVLampA_T2			
UV A base temperature	TE_UV_BASE_SDTa			
UV LAMP B UV output (intensity monitor)	DE_UVLampB_OUT			
UV LAMP B current	CE_UVLampB_I			
UV LAMP B Bulb temperature	TE_UVLampB_T2			
UV B base temperature	TE_UV_BASE_SDTb			
time	N/A			

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P*0888 Rev.* – Page 12 of 23

L.1.9 Using BNC cables, connect the Cs-Te photodiode "R" or "readout" BNC to the picoammeter and the "G" or "bias" BNC to –25 VDC on the HP DC power supply. Record the S/N of the Cs-Te photodiode and its sensitivity in Table L.1.2 below.

L.1.10 Command all optical switches to lamp A.

Action	CSTOL Command
Switch 1a to lamp A (pulse switch)	Set ECU OptSw1Mode with Ecu_Side 1, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical Switch P switch 1a pulse
(10.00 0	
Switch 1b to lamp A (pulse switch)	Set ECU OptSw1Mode with Ecu_Side 2, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical_Switch_P switch_1b_pulse
Switch 2a to lamp A (pulse switch)	Set ECU OptSw2Mode with Ecu_Side 1, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical_Switch_P switch_2a_pulse
,	
Switch 2b to lamp A (pulse switch)	Set ECU OptSw2Mode with Ecu_Side 2, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical_Switch_P switch_2b_pulse
Switch 3a to lamp A (pulse switch)	Set ECU OptSw3Mode with Ecu_Side 1, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical_Switch_P switch_3a_pulse
Switch 3b to lamp A (pulse switch)	Set ECU OptSw3Mode with Ecu_Side 2, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical_Switch_P switch_3b_pulse
Switch 4a to lamp A (pulse switch)	Set ECU OptSw4Mode with Ecu_Side 1, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical_Switch_P switch_4a_pulse
Switch 4b to lamp A (pulse switch)	Set ECU OptSw4Mode with Ecu_Side 2, Lamp_Side Lamp_a Set ECU PulsOptSw with Optical_Switch_P switch_4b_pulse

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P0888 Rev. – Page 13 of 23

L.1.11 Using the Cs-Te photodiode and a SMA-LEMO fiber optic jumper, measure the UV flux at each of the fiberoptic cable LEMO connectors listed in Table L.1.2 below. Also record the intensity monitor (DE_UVLampA_OUT) at the time of each measurement. The measured UV power for each fiber should be > 0.4 uW. An increase of as much as 15% may be obtained by loosening the SMA connector at the ECU interface, rotating the connector body 180 degrees and then re-tightening the connector to its torque specification (nominally 4 – 6 inlbs.). Perform this operation on any of the connectors whose output measures below 0.4 uW and check the appropriate box in table L.1.2 below. Record the final measured values in Table L.1.2 using the same boxes as the initial measurements with a slash ('/') dividing the before / after SMA rotation value.

TABLE L.1.2 - ECU UV OUTPUT - LAMP A

Command	CABLE / FIBER (ECU SMA)	picoammeter (-nA)	UV power @ 254 nm (uW)	DE_UVLampA_OUT (counts)	UV>0.4 uW (Y/N)	Re- torqued (Y/N)
Optical Switch 1A	W300/L4					
to Lamp-A	(ECU F4)					
Optical Switch 1B	W302/L2					
to Lamp-A	(ECU F10)					
Optical Switch 2A	W302/L4					
to Lamp-A	(ECU F12)					
Optical Switch 2B	W302/L3					
to Lamp-A	(ECU F11)					
Optical Switch 3A	W301/L1					
to Lamp-A	(ECU F5)					
Optical Switch 3B	W301/L2					
to Lamp-A	(ECU F6)					
Optical Switch 4A	W301/L3					
to Lamp-A	(ECU F7)					
Optical Switch 4B	W301/L4					
to Lamp-A	(ECU F8)					
Cs-Te photodiode S/N			Sensitivity			
Model <u>Cs-Te M-D-L</u>				(nA/uW)		

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P0888 Rev. – Page 14 of 23

- L.1.12 Record the final value of the lamp telemetry in Table L.1.1 above.
- L.1.13 Power down the RF exciter and the thermoelectric heater/cooler on lamp A by commanding:

Action	CSTOL Command
UV Lamp-A + 5V OFF	Set ECU UvLamp5V with Ecu_Side 1,Switch_Mode off
UV Lamp-A + 30V OFF	Set ECU UvLamp30V with Ecu_Side 1,Switch_Mode off
Time:	

L.1.14 Turn on the thermoelectric heater/cooler and the RF exciter on UV lamp B by commanding:

Action	CSTOL Command
UV Lamp-B + 5V ON	Set ECU UvLamp5V with Ecu_Side 2,Switch_Mode on
UV Lamp-B + 30V ON	Set ECU UvLamp30V with Ecu_Side 2,Switch_Mode on
Time:	

- L.1.15 Record the lamp telemetry in Table L.1.3 below.
- L.1.16 Allow the lamp to warm for 20 minutes or until the Test Lead has determined the lamp output is stable enough to perform a measurement. Record the lamp telemetry in Table L.1.3 below.

TABLE L.1.3 - Lamp Telemetry w/Lamp A Off, Lamp B On

Item	Mnemonic	initial value (step L.1.15) (counts)	warm value (step L.1.16) (counts)	final value (step L1.20) (counts)
UV LAMP A UV output (intensity monitor)	DE_UVLampA_OUT			
UV LAMP A current	CE_UVLampA_I			
UV LAMP A Bulb temperature	TE_UVLampA_T2			
UV A base temperature	TE_UV_BASE_SDTa			
UV LAMP B UV output (intensity monitor)	DE_UVLampB_OUT			
UV LAMP B current	CE_UVLampB_I			
UV LAMP B Bulb temperature	TE_UVLampB_T2			
UV B base temperature	TE_UV_BASE_SDTb			
time	N/A			

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P*0888 Rev.* – Page 15 of 23

- L.1.17 Connect the Cs-Te photodiode "R" or "readout" BNC to the picoammeter and the "G" or "bias" BNC to –25 VDC on the HP DC power supply. Record the S/N of the Cs-Te photodiode and its sensitivity in Table L.1.4 below.
- L.1.18 Command all optical switches to lamp B.

Action	CSTOL Command
Switch 1a to lamp B	Set ECU OptSw1Mode with Ecu_Side 1, Lamp_Side Lamp_b Set ECU PulsOptSw with Optical_Switch_P switch_1a_pulse
(pulse switch)	Set ECO Pulsopisw with Optical_Switch_P switch_ra_pulse
Switch 1b to lamp B	Set ECU OptSw1Mode with Ecu_Side 2, Lamp_Side Lamp_b
(pulse switch)	Set ECU PulsOptSw with Optical_Switch_P switch_1b_pulse
Switch 2a to lamp B (pulse switch)	Set ECU OptSw2Mode with Ecu_Side 1, Lamp_Side Lamp_b Set ECU PulsOptSw with Optical Switch P switch 2a pulse
(puise switch)	Set ECO FulsOptSw with Optical_Switch_F switch_za_pulse
Switch 2b to lamp B	Set ECU OptSw2Mode with Ecu_Side 2, Lamp_Side Lamp_b Set ECU PulsOptSw with Optical Switch P switch 2b pulse
(pulse switch)	Set ECO FulsOptSw with Optical_Switch_F switch_2b_pulse
Switch 3a to lamp B (pulse switch)	Set ECU OptSw3Mode with Ecu_Side 1, Lamp_Side Lamp_b
(puise switch)	Set ECU PulsOptSw with Optical_Switch_P switch_3a_pulse
Switch 3b to lamp B (pulse switch)	Set ECU OptSw3Mode with Ecu_Side 2, Lamp_Side Lamp_b Set ECU PulsOptSw with Optical Switch P switch 3b pulse
(puise switch)	Set EGO Fulsopisw with Optical_Switch_F switch_sb_pulse
Switch 4a to lamp B	Set ECU OptSw4Mode with Ecu_Side 1, Lamp_Side Lamp_b
(pulse switch)	Set ECU PulsOptSw with Optical_Switch_P switch_4a_pulse
Switch 4b to lamp B	Set ECU OptSw4Mode with Ecu_Side 2, Lamp_Side Lamp_b
(pulse switch)	Set ECU PulsOptSw with Optical_Switch_P switch_4b_pulse

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P0888 Rev. – Page 16 of 23

L.1.19 Using the Cs-Te photodiode and a SMA-LEMO fiber optic jumper, measure the UV flux at each of the fiberoptic cable LEMO connectors listed in Table L.1.4 below. Also record the intensity monitor (DE_UVLampB_OUT) at the time of each measurement. The measured UV power for each fiber should be > 0.4 uW. An increase of as much as 15% may be obtained by loosening the SMA connector at the ECU interface, rotating the connector body 180 degrees and then re-tightening the connector to its torque specification (nominally 4 – 6 inlbs.). Perform this operation on any of the connectors whose output measures below 0.4 uW and check the appropriate box in table L.1.2 below. Record the final measured values in Table L.1.4 using the same boxes as the initial measurements with a slash ('/') dividing the before / after SMA rotation value.

TABLE L.1.4 - ECU UV OUTPUT - LAMP B

Command	CABLE / FIBER (ECU SMA)	picoammeter (-nA)	UV power @ 254 nm (uW)	DE_UVLampB_OUT (counts)	UV>0.4 uW (Y/N)	Re- torqued (Y/N)
Optical Switch 1A	W300/L4					
to Lamp-B	(ECU F4)					
Optical Switch 1B	W302/L2					
to Lamp-B	(ECU F10)					
Optical Switch 2A	W302/L4					
to Lamp-B	(ECU F12)					
Optical Switch 2B	W302/L3					
to Lamp-B	(ECU F11)					
Optical Switch 3A	W301/L1					
to Lamp-B	(ECU F5)					
Optical Switch 3B	W301/L2					
to Lamp-B	(ECU F6)					
Optical Switch 4A	W301/L3					
to Lamp-B	(ECU F7)					
Optical Switch 4B	W301/L4					
to Lamp-B	(ECU F8)					
Cs-Te photodiode S/N			Sensitivity			
Model <u>Cs-Te M-D-L</u>				(nA/uW)		

14 December, 2001

(PTP) UV Cable Continuity Check Procedure No. P0888 Rev. –

Page 17 of 23

L.1.20	Record the final value of the lamp telemetry in Table L.1.3 above.			
L.1.21	Power down the RF exciter and the	thermoelectric heater/cooler on lamp B by commanding:		
	Action	CSTOL Command		
	UV Lamp-B + 5V OFF UV Lamp-B + 30V OFF	Set ECU UvLamp5V with Ecu_Side 2,Switch_Mode off Set ECU UvLamp30V with Ecu_Side 2,Switch_Mode off		
	Time:			
L.1.22	Confirm that +5 V power to both	lamp A and B is off.		
L.1.23	Power down the telemetry for both	lamps A and B by commanding:		
	Action	CSTOL Command Set ECU UvLamp15V with Ecu_Side 1,Switch_Mode off		
	UV Lamp-A +/- 15 V OFF UV Lamp-B +/- 15 V OFF	Set ECU UvLamp15V with Ecu_Side 1,Switch_Mode off Set ECU UvLamp15V with Ecu_Side 2,Switch_Mode off		
	Time:			
L.1.24	Stop the nitrogen purge and remov	e the purge line from the ECU.		
L.1.25	LEMO connector as a function of the	tate of the UV power that will be delivered to the top hat the lamp intensity monitor. This data along with the 3 and P0431AB may be used to estimate UV power at the sity monitors.		
SECTION	COMPLETEDDATE	AT TIME		
SIGNED: _	TEST LEAD	PRINT NAME:		
SIGNED:_	QA REPRESENTATIVE	PRINT NAME:		

Procedure No. P*0888 Rev.* – Page 18 of 23

L.2 CONFIRM FLIGHT FIBER OPTIC CABLES CONNECTION AT ECU

SECTION S	TARTED/ DATE	ATTIME
SIGNED:	TEST LEAD	PRINT NAME:
SIGNED:	QA REPRESENTATIVE	PRINT NAME:

L.2.1 Based on the data collected in section L.1 and on visual inspection of the spare fiber connections (e.g. fibers not connected to a UV switch in the ECU), confirm the connections in Table L.2.1 below. Enter the measured UV power from tables L.1.2 and L.1.4 in the appropriate boxes.

TABLE L.2.1 – UV FIBER OPTIC CABLE ASSIGNMENTS

UV Switch	ECU	CABLE/FIBER	MEASURED UV	MEASURED UV POWER (uW)	
			LAMP A	LAMP B	
	ECU F1	W300/L1	N/A	N/A	
	ECU F2	W300/L2	N/A	N/A	
	ECU F3	W300/L3	N/A	N/A	
1a	ECU F4	W300/L4			
3a	ECU F5	W301/L1			
3b	ECU F6	W301/L2			
4a	ECU F7	W301/L3			
4b	ECU F8	W301/L4			
	ECU F9	W302/L1	N/A	N/A	
1b	ECU F10	W302/L2			
2b	ECU F11	W302/L3			
2a	ECU F12	W302/L4			

Gravity Probe B 14 December, 2001

(PTP) UV Cable Continuity Check Procedure No. P0888 Rev. – Page 19 of 23

SECTION COMPLETED			A	AT	
		DATE		TIME	
SIGNED:				PRINT NAME:	
	TEST LEAD				
SIGNED:				PRINT NAME:	
	QA REPRESI	ENTATIVE			

14 December, 2001

Procedure No. P*0888 Rev.* – Page 20 of 23

1.3	REDUCE	VIID		
1 .5	BEI////		ABL.DIVE	11414

SECTION S	TARTEDDATE	AT TIME	
SIGNED: _	TEST LEAD	PRINT NAME:	
SIGNED:	QA REPRESENTATIVE	PRINT NAME:	

- L.3.1 Use the embedded Excel spreadsheet (Tables L.3.3) at the end of this procedure to estimate the UV power expected at the top hat connectors for each UV fiber / UV lamp combination.
- L.3.2 Calculate the number minutes each of the power lines were on for each lamp, the number of power line on/off cycles and the number of ½ cycles for each optical switch and update Table L.3.1 below.

TABLE L.3.1 – Lamp and Switch Usage Log

	+/- 15V		+ 5 V		+ 30 V		
	time on	on/off	time on	on/off	time on	on/off	
	(min)	cycles	(min)	cycles	(min)	cycles	
Lamp A							
Lamp B							
Switch (1/2	cycles)						
1a	1b	2a	2b	3a	3b	4a	4b

14 December, 2001

(PTP) UV Cable Continuity Check Procedure No. P0888 Rev. -

Page 21 of 23

L.7.3	At test completion, the following shall be archived on the Payload Server: An electronic copy of the 'as built' of this procedure. Any raw data files collected during the implementation of this procedure.				
	Server path:				
L.7.4	The original 'As-Built' hard copy of this doct	ument shall be kept as part of:			
SECTION	ON COMPLETED	ATTIME			
SIGNE	D: TEST LEAD	PRINT NAME:			
SIGNE	D:QA REPRESENTATIVE	PRINT NAME:			
Test co	ompleted.	Completed by:			
		Date:			

14 December, 2001

(PTP) UV Cable Continuity Check

Procedure No. P*0888 Rev.* – Page 22 of 23

The results obtained in the performance of this procedure are acceptable: Test Engineer(s) SIGNED: _____PRINT:_____ DATE:_____ SIGNED: ____PRINT:____ DATE:_____ SIGNED: _____PRINT:____ DATE:_____ Test Lead SIGNED: ____PRINT:____ DATE:____ The information obtained under this assembly and test procedure is as represented and the documentation is complete and correct: **Payload Test Director** SIGNED: ______PRINT:_____ DATE:____ **QA** Representative SIGNED: PRINT: DATE:____ **Program QA Engineer** SIGNED: PRINT: DATE:____

14 December, 2001 Procedure No. P 0888 Rev. — Page 23 of 23

TABLE L.3.2 - PROBE C UV OPTICAL AND BIAS CONNECTIONS

[Bias and Ground Plane pin assignments and optical losses are per P0429AB and P0431AB]

GYRO	UV fixture	Top Hat LEMO	BIAS Connector Pin #	Ground Plane @ Top Hat	Optical losses w/ LEMOs (dB)	Optical losses w/o LEMOs (dB)
1	Α	PM IIII	BGPM - 4	CG18	4.75	1.70
	В	UV12 II	BG34 -1		5.73	2.69
2	Α	UV12 IIII	BG34 - 3	CG28	6.35	3.30
	В	UV12 III	BG34 - 4		6.43	3.38
3	Α	UV34 I	BG12 -1	CG38	6.09	3.04
	В	UV34 II	BG12 -2		6.73	3.68
4	Α	UV34 III	BG12 -3	CG48	5.88	2.83
	В	UV34 IIII	BG12 -4		5.58	2.53

TABLE L.3.3 - LAMP MONITOR CALIBRATION

ECU UV OUTPUT	measured UV	(uW)	intensity monitor	(counts)	estimated UV @ top hat	(uW)	normalized UV at top hat	(uW/count)
switch #	Lamp A	Lamp B	Lamp A	Lamp B	Lamp A	Lamp B	Lamp A	Lamp B
1a					0.000	0.000	#DIV/0!	#DIV/0!
1b					0.000	0.000	#DIV/0!	#DIV/0!
2a					0.000	0.000	#DIV/0!	#DIV/0!
2b					0.000	0.000	#DIV/0!	#DIV/0!
3a					0.000	0.000	#DIV/0!	#DIV/0!
3b					0.000	0.000	#DIV/0!	#DIV/0!
4a					0.000	0.000	#DIV/0!	#DIV/0!
4b					0.000	0.000	#DIV/0!	#DIV/0!

Assumed LEMO connector loss (dB)

2.5