

# GRAVITY PROBE B PROCEDURE FOR SCIENCE MISSION DEWAR

## Internal Guard Tank Fill – Guard Tank Vent Line Connected

**THIS PROCEDURE CONTAINS HAZARDOUS OPERATIONS**

### P0211 REV. D

Jan 15, 2002

ECO 1328

Revised by

\_\_\_\_\_ Date \_\_\_\_\_

Ned Calder  
Cryogenic Test

Checked by

\_\_\_\_\_ Date \_\_\_\_\_

Dave Murray  
Cryogenic Test

Approvals:

\_\_\_\_\_ Date \_\_\_\_\_

Dorrene Ross  
Quality Assurance

\_\_\_\_\_ Date \_\_\_\_\_

Harv Moskowitz  
LMMS Safety

\_\_\_\_\_ Date \_\_\_\_\_

Rob Brumley  
Payload Technical Manager

\_\_\_\_\_ Date \_\_\_\_\_

Mike Taber  
Payload Test Director

**REVISION RECORD**

REV	ECO	PAGES	DATE
A	770	<p>Added instrument calibration requirements, E.</p> <p>Added changes to Gas Module to accommodate Guard Tank bypass mode, G.2, G.6.3, G.7.6, G.9, G.10, and figure 1.</p> <p>Modified G.3.1 such that smaller volume is used in checking initial pressure in Fill Line.</p> <p>Identified RAV selection switches G.3.2.5, G.6.2.3.</p>	3/6/98
B	773	<p>Incorporated option for simultaneous filling of Well, added section G.7.</p> <p>Added step G.8.1.5.</p> <p>Added closure of AV-3 in G.9.11.</p> <p>Added case for evacuated well, broke procedure into case1 and case2, G.1.2, G.2.6, and G.11.2.</p>	4/29/98
C	1087	<p>Changed title from <i>Internal Main Tank to Guard Tank Transfer to Internal Guard Tank Fill – Vent Lines Connected</i> to distinguish from similar procedure with vent lines disconnected.</p> <p>Section A – Revised scope to accurately summarize content of procedure.</p> <p>Section B – Divided into two sections, addressing safety issues (new Section B) and test personnel (new Section D).</p> <p>Reorganized safety paragraphs into: hazards, mitigation, injuries. Content of both new sections essentially unchanged.</p> <p>Added Quality Assurance Section (new Section C)</p> <p>Section C, D, and E – Consolidated all requirements into new Section E entitled Requirements. Added Configuration requirements, GSE/SMD interface requirements, alarm setup requirements, vacuum requirements, and non-flight hardware requirements.</p> <p>Section G.1 Added section to verify notification of QA.</p> <p>Section G.2 – Added steps to verify configuration requirements and alarm setup. Added GT to level alarm list (setpoint = 10%)</p> <p>Section G.3 – Added section to verify Gas Module in Standard Configuration.</p> <p>Changed order of steps in Sections G.7 and G.8 from close MT vent, turn on MT heater, set up DAS, open RAV-2 to set up DAS, prepare RAV-2 for activation, close MT vent, turn on MT heater, activate RAV-2.</p> <p>Changed to require manifolding of MT and GT vent lines at end of procedure.</p> <p>Added caution to monitor temperatures at Station 200 and top of lead bag during MT vent closure.</p> <p>Added caution to monitor and maintain positive GT pressure.</p>	2/17/00
D	1328	Changed Title	1/15/02

	<p>Updated procedure to include steps necessary for having either the MT vent line connected or disconnected Removed all references to internal Well fills Added Hazardous Materials comment to title Page. Added QA inspection points Added minor redlines Added step to verify purity of helium gas Modified sections B.2.2. and B.3.1 to reflect new location of SMD in Lockheed Martin building 205 Added sections B.2.3 "Other Hazards", B.3.2 "Hardware Mishap", B.3.3 "Contingency Response". Updated Qualified Personnel List Added EM SYS229 Added Appendix Contingency Responses Added pre/post checklist tables Updated Figures</p>	
--	--	--

**Table of Contents**

A. SCOPE	1
B. SAFETY	1
B.1. Potential Hazards	
B.2. Mitigation of Hazards	
B.3. Injuries	
C. QUALITY ASSURANCE	
C.1. QA Notification	
C.2. Red-line Authority	
C.3. Discrepancies	
D. TEST PERSONNEL	
D.1. Personnel Responsibilities	
D.2. Personnel Qualifications	
D.3. Qualified Personnel	
E. REQUIREMENT	
E.1. Electrostatic Discharge Requirements	
E.2. Lifting Operation Requirements	
E.3. Hardware/Software Requirements	
E.4. Instrument Pretest Requirements	
E.5. Configuration Requirements	
E.6. Optional Non-flight Configurations	
F. REFERENCE DOCUMENTS	
F.1. Drawings	
F.2. Supporting documentation	
F.3. Additional Procedures	
G. OPERATIONS	
G.1. Pre-Operations Verifications	
G.2. Verify Purity of All Sources of Helium Gas	
G.3. Verify Configuration Requirements	
G.4. Establish Gas Module Configuration and Record Initial Conditions	
G.5. Verify SMD in Standard Configuration	
G.6. Check Initial pressure in Fill Line	
G.7. Raise Pressure in Fill Line by opening RAV-1	
G.8. Set up Data Acquisition	
G.9. Prepare to Transfer	
G.10. Initiate Transfer	
G.11. Terminate Transfer to Guard Tank	
G.12. Condition Dewar Fill Line and Fill Cap Assembly.	
G.13. Configure the DAS and Liquid Level Sensors	
G.14. Verify Final Configuration	

**List of Abbreviations and Acronyms**

AG-x	Gauge x of Gas Module auxiliary section	MT	Main Tank
AMI	American Magnetics Inc.	MTVC	Main Tank Vent Cap
ATC	Advanced Technology Center	MTVC-G	Main Tank Vent Cap pressure gauge
Aux	Auxiliary	MTVC-RV	Main Tank Vent Cap relief valve
AV-x	Valve x of Gas Module auxiliary section	MTVC-V	Main Tank Vent Cap valve
Bot	Bottom	NBP	Normal boiling point
CN [xx]	Data acquisition channel number	ONR	Office of Naval Research
DAS	Data Acquisition System	PFCG	Fill Cap assembly pressure Gauge
EFM	Exhaust gas Flow Meter	PFM	Pump equipment Flow Meter
EG-x	Gauge x of Gas Module exhaust section	PG-x	Gauge x of Pump equipment
EM	Electrical Module	PM	Pump Module
ERV-x	Relief valve of Gas Module exhaust section	psi	pounds per square inch
EV-x	Valve number x of Gas Module exhaust section	psig	pounds per square inch gauge
FCV	Fill Cap Valve	PTD	Payload Test Director
FIST	Full Integrated System Test	PV-x	Valve x of the Pump equipment
GHe	Gaseous Helium	QA	Quality Assurance
GM	Gas Module	RAV-x	Remote Actuated Valve-x
GP-B	Gravity Probe-B	RGA	Residual Gas Analyzer
GSE	Ground Support Equipment	SMD	Science Mission Dewar
GT	Guard Tank	STV	SMD Thruster vent Valve
GTVC	Guard Tank Vent Cap	SU	Stanford University
GTVC-G	Guard Tank Vent Cap pressure gauge	SV-x	SMD Valve number x
GTVC-RV	Guard Tank Vent Cap relief valve	TG-x	Gauge x of Utility Turbo System
GTVC-V	Guard Tank Vent Cap valve	TV-x	Valve x of Utility Turbo System
GTV-G	Guard Tank vent pressure gauge	UTS	Utility Turbo System
GTV-RV	Guard Tank vent relief valve	Vac	Vacuum
GTV-V	Guard Tank vent valve	VCP-x	Vent cap pressure gauge
HX-x	Vent line heat exchanger in Gas Module	VCRV-x	Vent cap relief valve
KFxx	Quick connect o-ring vacuum flange (xx mm diameter)	VCV-x	Vent cap valve
LHe	Liquid Helium	VDC	Volts Direct Current
LHSD	Liquid Helium Supply Dewar	VF-x	Liquid helium Fill line valve
Liq	Liquid	VG-x	Gauge x of Vacuum Module
LL	Liquid level	VM	Vacuum Module
LLS	Liquid level sensor	VV-x	Valve x of Vacuum Module
LMMS	Lockheed Martin Missiles and Space	VW-x	Valve x of Dewar Adapter
LMSC	Lockheed Missiles and Space Co.		

**A. SCOPE**

This procedure describes the steps necessary to transfer normal boiling point liquid helium from the Main Tank to the Guard Tank of the Science Mission Dewar. This procedure requires that the Guard Tank vent line is connected to the Gas Module. The steps include;

- Raise internal fill line pressure to Main Tank pressure – open RAV-1.
- Increase Main Tank pressure – close vent valve, turn on heater.
- Initiate transfer – open RAV-2.
- Terminate transfer – close RAV-1 and RAV-2.
- Reestablish Main Tank venting.

The Main Tank vent line may either be connected or disconnected from the Gas Module.

**B. SAFETY****B.1. Potential Hazards**

Personal injury and hardware damage can result during normal positioning, assembly and disassembly of hardware. Examples include: positioning Dewar in tilt stand; integrating probe with airlock; positioning airlock on Dewar; removing airlock from Dewar; removing probe from Dewar; and positioning support equipment such as pressurized gas cylinders and supply dewars.

A number of undesired events may be associated with these operations. For example, personnel or equipment can be struck when hardware is being moved (e.g. by forklift or crane load). Personnel are subject to entrapment while positioning hardware, such as hands or feet caught between objects as hardware is moved into place. Suspended hardware may be dropped. Personnel can be caught between objects such as forklifts and walls or loads and building support columns.

In addition, liquid helium used in the SMD represents a hazardous material for the personnel involved in the operations. Cryogenic burns can be caused by contact with the cold liquid or gas, high pressures can result if boiling liquid or cold gas is confined without a vent path, and asphyxiation can result if the vent gas is allowed to accumulate.

The SMD Safety Compliance Assessment, document GPB-100153C discusses the safety design, operating requirements and the hazard analysis of the SMD.

**B.2. Mitigation of Hazards****B.2.1. Lifting hazards**

There are no lifting operations in this procedure

**B.2.2. Cryogenic Hazards**

The high bay, LM Building 205, has an oxygen deficiency monitor that alarms when the oxygen level is reduced to 19.5%. Additional

temperature and pressure alarms, provided by the DAS, warn of potential over-pressure conditions. Emergency vent line deflectors are installed over the four burst disks on the SMD vacuum shell.

Only authorized and trained LM and SU personnel are allowed in the high-bay without escort. All personnel working at a height 30 inches or more off the floor are required to have an LM approved air tank within easy reach. In the unlikely event of a large LHe spill all employees have been instructed to evacuate the room and contact LM safety.

The following additional requirements apply to all personnel involved directly in cryogenic operations. Gloves that are impervious to liquid helium and liquid nitrogen are to be worn whenever the possibility of splashing or impingement of high-velocity cryogenics exists or when handling equipment that has been cooled to cryogenic temperatures. Protective clothing and full-face shields are to be worn whenever the possibility of splashing cryogenics exists.

#### B.2.3. Other Hazards

When appropriate, tools or other items used with the potential to damage the SMD or Probe shall be tethered.

### B.3. Mishap Notification

#### B.3.1. Injury

In case of any injury obtain medical treatment as follows  
LM **Call 117**

#### B.3.2. Hardware Mishap

In case of an accident, incident, or mishap, notification is to proceed per the procedures outlined in Lockheed Martin Engineering Memorandum EM SYS229.

#### B.3.3. Contingency Response

Responses to contingencies (e.g., power failure) are listed in Appendix 3.

## C. QUALITY ASSURANCE

### C.1. QA Notification

***The NASA representative and SU QA shall be notified 24 hours prior to the start of this procedure.*** Upon completion of this procedure, the QE Manager will certify his/her concurrence that the effort was performed and accomplished in accordance with the prescribed instructions by signing and dating in the designated place(s) in this document.

### C.2. Red-line Authority

Authority to red-line (make minor changes during execution) this procedure is given solely to the PTD or his designate and shall be approved by the QA Representative. Additionally, approval by the Payload Technical Manager shall be required, if in the judgement of the PTD or QA Representative, experiment functionality may be affected.

### C.3. **Discrepancies**

A Quality Assurance Representative designated by D. Ross shall review any discrepancy noted during this procedure, and approve its disposition. Discrepancies will be recorded in a D-log or a DR per Quality Plan P0108. Any time a procedure calls for verification of a specific configuration and that configuration is not the current configuration, it represents a discrepancy of one of three types. These types are to be dealt with as described below.

1. If the discrepancy has minimal effect on procedure functionality (such as the state of a valve that is irrelevant to performance of the procedure) it shall be documented in the procedure, together with the resolution. Redlines to procedures are included in this category.
2. If the discrepancy is minor and affects procedure functionality but not flight hardware fit or function, it shall be recorded in the D-log. Resolution shall be in consultation with the PTD and approved by the QA representative.
3. All critical and major discrepancies, those that effect flight hardware fit or functions, shall be documented in a D-log and also in a Discrepancy Report, per P0108.

## D. **TEST PERSONNEL**

### D.1. **Personnel Responsibilities**

The performance of this procedure requires a minimum complement of personnel as determined by the Test Director. The Test Director is the designated signer for the “witnessed by” sign-off located at the end of each procedure. The person in charge of the operation (Test Director or Test Engineer) is to sign the “completed by” sign-off. ***The Test Director will perform Pre-Test and Post-Test Briefings in accordance with P0875 “GP-B Maintenance and Testing at all Facilities.” Checklists will be used as directed by P0875***

### D.2. **Personnel Qualifications**

The Test Director must have a detailed understanding of all procedures and facility operations and experience in all of the SMD operations. Test Engineers must have SMD Cryogenic operations experience and an understanding of the operations and procedures used for the cryogenic servicing/maintenance of the Dewar.

### D.3. **Qualified Personnel**

The names of those actually performing this procedure are to be initialed and the name of the person acting as Test Director should be circled.



<b><i>Test Director</i></b>	<b><i>Test Engineer</i></b>
Mike Taber Dave Murray Ned Calder	Tom Welsh Ned Calder

## E. REQUIREMENTS

### E.1. Electrostatic Discharge Requirements

This procedure does not include any equipment sensitive to electrostatic discharge.

### E.2. Lifting Operation Requirements

There are no lifting operations in this procedure

### E.3. Hardware/Software Requirements

#### E.3.1. Commercial Test Equipment

No commercial test equipment is required for this operation.

#### E.3.2. Ground Support Equipment

The Ground Support Equipment includes the Gas Module, the Pump Module, the Electrical Module, and the Vacuum Module. The Gas Module (Figure 1) provides the capability to configure vent paths, read pressures and flow rates, and pump and backfill vent lines. The Pump Module provides greater pumping capacity than the Gas Module, together with additional flow metering capabilities. The vent output of the Gas Module flows through the Pump Module. The Electrical Module contains the instruments listed in Table 1, and provides remote control of valves in the Gas Module, Pump Module, and SMD. The Vacuum Module contains a turbo pump, backed by a vane pump, and provides the capability to pump out the SMD vacuum shell.

This procedure calls for use of hardware located in the Gas and Electrical Modules.

#### E.3.3. Computers and Software:

The Data Acquisition System (DAS) is required for this procedure. The DAS reads and displays pressures, temperatures, and flow rates and monitors critical parameters. No additional computers or software are required.

#### E.3.4. Additional Test Equipment

#### E.3.5. Additional Hardware

<i>Description</i>
Main Tank vent cap assembly – See Figure 2

## E.3.6. Tools

<i>Description</i>
Torque Wrench, 1-1/4-in socket, 60 +/- 5 in-lb Cal Due Date: _____ S/N

## E.3.7. Expendables

<i>Description</i>	<i>Quantity</i>	<i>Mfr./Part No.</i>
Ethanol	AR	N/A
99.99% pure gaseous helium	AR	N/A
Vacuum Grease	AR	Dow Corning High Vacuum or Apiezon N

## E.4. Instrument Pretest Requirements

The GSE instruments required to perform this procedure are listed in Table 1, together with their serial numbers, where available. Instruments that are required to have current calibrations are indicated in the Cal-Required column. Instruments that do not require calibration are those not used to verify performance requirements and are not connected to flight instrumentation. The status column is to be filled in with the due date of the instrument calibration sticker and verified to be in calibration by QE or QE designee.

**Table 1. Required Instrumentation and Calibration Status**

<i>No.</i>	<i>Location</i>	<i>Description</i>	<i>User Name</i>	<i>Serial No.</i>	<i>Cal Required</i>	<i>Status Cal due date</i>
1	DAS	Power Supply, H-P 6627A	-	3452A01975	Yes	
2	DAS	Power Supply, H-P 6627A	-	3452A01956	Yes	
3	DAS	Data Acquisition/Control Unit H-P 3497A	-	2936A245539	No	-
4	DAS	Digital Multimeter H-P 3458A	-	2823A15047	Yes	
5	EM	Vacuum Gauge Controller Granville-Phillips Model 316	EG-1a, -1b	2827	No	-
6	EM	Vacuum Gauge Controller Granville-Phillips Model 316	AG-2a, -2b	2826	No	-
7	EM	Vacuum Gauge Controller Granville-Phillips Model 316	EG-3	2828	No	-
8	EM	MKS PDR-C-2C	EG-2, FCG	92022108A	No	-
9	EM	Flow meter – Matheson 8170	EFM-1	96186	No	-
10	EM	Flow meter totalizer Matheson 8124	EFM-1	96174	No	-
11	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Main Tank	96-409-11	No	-

No.	Location	Description	User Name	Serial No.	Cal Required	Status Cal due date
12	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Guard Tank	96-409-10	No	-
13	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Well	96-409-9	No	-
14	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Axial Lock	96-409-12	No	-
15	EM	Pressure Controller – MKS 152F-92	EV-7a, -7b	96203410A	No	-
16	EM	Power Supply HP 6038A	H08D Tank Heater	96023407A	Yes	
17	EM	Power Supply HP 6038A	H09D Tank Heater	3511A-13332	Yes	
18	EM	Power Supply HP 6038A	RAV Power Supply	3329A-12486	Yes	
19	EM	Vac Ion Pump power supply Varian 929-0910, Minivac	SIP	5004N	No	-
20	EM	Flow meter totalizer Veeder-Root	PFM-1	576013-716	No	-
21	GM	Pressure Gauge, Heise	AG-1	CC-122077	No	-
22	GM	Pressure Gauge, Marshall Town	AG-3	N/A	No	-
23	GM	Main Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller	-	C-19950	No	-
24	GM	Guard Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller	-	C-09920	No	-
25	VM	Vacuum Gauge readout, Granville-Phillips 316	VG-3 VG-4	2878	No	-
26	VM	Vacuum Gauge readout, Granville-Phillips 360	VG-1, VG-2 VG-5	96021521	No	-

#### E.5. Configuration Requirements

##### E.5.1. Main Tank

Liquid in the Main Tank must be at its normal boiling point (NBP)

##### E.5.2. Guard Tank

The Guard Tank may contain liquid or be depleted.

##### E.5.3. Well

The Well must be evacuated.

##### E.5.4. SMD Vacuum Shell

The Vacuum Shell pressure must be less than  $5 \times 10^{-5}$  torr.

Document No. P0213, *Connect Vacuum Module to SMD*, contains the procedure for connecting to and pumping on the SMD vacuum shell.

## E.5.5. Alarm System

1. The DAS alarm system must be enabled and contain the following alarm set-points:
  - a. Station 200 temperature (CN 01) set at  $T \leq 6.5$  K.
  - b. Top of lead bag temperature set (CN 28) at  $T \leq 6.0$  K.
  - c. Relative Guard Tank Pressure (CN 46) set at  $P \geq 0.3$  torr.
- 2.

## E.5.6. GSE and Non-flight Hardware

1. The flight burst disk is installed at the SMD Fill Line.
2. The ion-pump magnet is installed.
3. GSE cabling must be connected between the SMD and the Electrical Module (P/N 5833812) and between the SMD and the Data Acquisition System (P/N 5833811).
4. The Guard Tank vent line must be connected to the Gas Module with a vacuum insulated line (P/N 5833813). Procedure No. P0676, *Connect Guard Tank Vent Line to Gas Module*, contains the procedures for connecting vent lines.
5. The Fill Cap Assembly must be installed at SV-13 (See Figure 3)
6. Dewar Adapter heaters on SMD must be installed and operational.

E.6. **Optional Non-flight Configurations**

The following modifications or non-flight arrangement of the basic SMD configuration may also be in place. They are incidental to the performance of this procedure and not required.

1. The SMV may be installed in its transportation and test fixture.
2. A foreign object and debris shield covers the upper cone of the SMD.

3. The Vacuum shell pump out port at SV-14 may be connected to the Vacuum Module (P/N 5833816) via a 2-in valve and pumping line, with the valve in either the closed position or in the open position. The Vacuum Module pump may be; off, actively pumping the pumping line up to a closed SV-6, or actively pumping the vacuum shell.
4. The thruster vent port is flanged to a shut-off valve.

## F. REFERENCE DOCUMENTS

### F.1. Drawings

<b>Drawing No.</b>	<b>Title</b>
LMMS-5833394	<i>Instrumentation Installation</i>

### F.2. Supporting documentation

<b>Document No.</b>	<b>Title</b>
LMMC-5835031	<i>GP-B Magnetic Control Plan</i>
GPB-100153C	<i>SMD Safety Compliance Assessment</i>
SU/GP-B P0141	<i>FIST Emergency Procedures</i>
LMSC-P088357	<i>Science Mission Dewar Critical Design Review</i>
SU/GP-B P0108	<i>Quality Plan</i>
LMMS GPB-100333	<i>Science Mission Dewar Failure Effects and Causes Analysis</i>
SU/GP-B P059	<i>GP-B Contamination Control Plan</i>
EM SYS229	<i>Accident/Mishap/Incident Notification Process</i>

### F.3. Additional Procedures

<b>Document No.</b>	<b>Title</b>
SU/GP-B P0674	<i>Connect Main Tank Vent Line to Gas Module – Main Tank at NBP</i>
SU/GP-B P0676	<i>Connect Guard Tank Vent Line to Gas Module</i>
SU/GP-B P0879	<i>Accident/Incident/Mishap Notification Process</i>
SU/GP-B P0213	<i>Connect Vacuum Module to SMD</i>
SU/GP-B	<i>GP-B Maintenance and Testing at all Facilities</i>

Operation Number: \_\_\_\_\_

Date Initiated: \_\_\_\_\_

Time Initiated: \_\_\_\_\_

**G. OPERATIONS**

**G.1. Pre-Operations Verifications**

- o Verify SU QA notified.  
Record: Individual notified \_\_\_\_\_,  
Date/time \_\_\_\_\_ / \_\_\_\_\_.
- o Verify ONR representative notified.  
Record: Individual notified \_\_\_\_\_,  
Date/time \_\_\_\_\_ / \_\_\_\_\_.
- o Record calibration due dates in Table 1 (Sections. E.3.4, E.4) and E.3.6
- o Persons actually performing this procedure should initial their names in Sec D.3 and the name of the Test Director should be circled.
- o Verify completion of the Pre-Operations Checklist (Appendix 1).
- o Verify Guard Tank Vent Line connected-if Guard Tank Vent Line is not connected terminate procedure.

QA Witness: \_\_\_\_\_

**G.2. Verify Purity of All Sources of Helium Gas**

G.2.1. Record serial number on helium bottle/s.

- |          |          |          |
|----------|----------|----------|
| 1. _____ | 2. _____ | 3. _____ |
| 4. _____ | 5. _____ | 6. _____ |

G.2.2. Verify helium bottle/s have been tested for purity and record Op. Number.

Op. Number: \_\_\_\_\_

Record Date: \_\_\_\_\_

QA Witness: \_\_\_\_\_

**G.3. Verify Configuration Requirements**

G.3.1. Verify proper sealing of Well. Record closure (cover plate, Hole cutter, Probe etc.). \_\_\_\_\_

G.3.2. Verify liquid in Main Tank at NBP (4.2<T<4.3) and record temperature at bottom of tank CN [09] \_\_\_\_\_K.

- G.3.3. Ensure ion-pump magnet installed.
- G.3.4. Ensure Vacuum Shell Pressure  $< 5 \times 10^{-5}$  torr.
1. Turn on Vac-ion pump and record time of day \_\_\_\_\_
  2. Use DAS [Monitor Data] for CN 99.
  3. When value is steady, record pressure (IP) \_\_\_\_\_ torr. If pressure is above  $1 \times 10^{-4}$  torr, turn off Vac-ion pump and perform procedure P0213, *Connect Vacuum Module to SMD*, to connect Vacuum Module and pump out SMD vacuum shell.
  4. Exit [Monitor Data] and collect data with [Set Data Interval] to 5 min.
  5. When data cycle is complete, turn off Vac-ion pump.

**CAUTION**

**This procedure necessitates closure of the Main Tank vent. During the period of closure the temperatures at station 200 and the top of the lead bag are to be continuously monitored by the test director. Ensure that these temperatures are on the DAS alarm list and appropriately alarmed.**

- G.3.5. Ensure DAS alarm system enabled and record set points.
1. **Station 200 temperature** – ensure CN [01] on DAS alarm list and set to alarm at  $T \leq 6.5$  K.  
Record set point. \_\_\_\_\_ K
  2. **Top of lead bag temperature** – ensure CN [28] on DAS alarm list and set to alarm at  $T \leq 6.0$  K.  
Record set point. \_\_\_\_\_ K
  3. **Relative Guard Tank Pressure** – ensure CN [46] on DAS alarm list and set to alarm at  $\Delta P \geq 0.3$  torr.  
Record set point. \_\_\_\_\_ torr
- G.3.6. Ensure liquid-level alarms enabled and record set points.
1. **Main Tank** – ensure liquid-level alarm set  $\geq 20\%$ .  
Record set point. \_\_\_\_\_ %
  2. **Guard Tank** – ensure liquid-level alarm set  $\geq 10\%$ .  
Record set point. \_\_\_\_\_ %
- G.3.7. Verify Flight Burst Disk installed on SMD internal fill-line.
- G.3.8. Ensure GSE cabling connected between SMD and Electrical Module and between SMD and Data Acquisition System.
- G.3.9. Ensure Guard Tank vent line connected to Gas Module. If not, perform procedure P0676, *Connect Guard Tank Vent Line to Gas Module*, to

connect Guard Tank vent.

G.3.10. Ensure Fill Cap Assembly installed at SV-13.

QA Witness:\_\_\_\_\_



**G.4. Establish Gas Module Configuration and Record Initial Conditions**

- G.4.1. Ensure Guard Tank Vent Valve (GTV-V) open.
- G.4.2. Ensure closed EV-4, EV-5, EV-8, EV-10, EV-12, EV-15, EV-19, EV-21/22, EV-24
- G.4.3. Ensure all AV valves closed
- G.4.4. Establish Guard Tank and Main Tank vent configurations.

**Initial Guard Tank Vent Configuration:**

- 
- o Guard Tank contains liquid and is venting in common manifold mode:
    - 1. Verify EV-13 and EV-16 open
    - 2. Verify EV-20 and EV-23 closed
- 
- o Guard Tank contains liquid and is venting in bypass mode:
    - 1. Verify EV-16 and EV-20 open
    - 2. Verify EV-13 and EV-23 closed
- 
- o Guard Tank depleted – pressure independently regulated to maintain positive pressure:
    - 1. Verify EV-16, EV-23 open
    - 2. Verify EV-20 and EV-13 closed
- 
- o Main Tank Vent Line Connected to Gas Module
    - 1. Verify EV-9 open
    - 2. Verify SV-9 open
    - 3. Verify EV-17 closed
- 
- o Main Tank Vent Line not connected to Gas Module
    - 1. Verify SV-9 open
-

G.4.5. Record pressures:

1. Guard Tank pressure (EG-1a) \_\_\_\_\_ torr.
2. Main Tank pressure (EG-3) \_\_\_\_\_ torr.

G.4.6. Record liquid helium levels:

1. Main Tank level (LL-1D or LL-2D) \_\_\_\_\_%
2. Guard Tank Level (LL-5D or LL-6D) \_\_\_\_\_%

G.4.7. Turn on pump AP-1.

G.4.8. Turn on Guard Tank vent-line heat exchanger (EH-2).

QA Witness: \_\_\_\_\_

**G.5. Verify SMD in Standard Configuration**

G.5.1. Using the RAV log book verify that the dewar's internal valves are in the following positions. If not, investigate to ensure previous RAV operations properly recorded. If necessary, note resolution in D-log.

1. Open: RAV-3, and RAV-6B.
2. Closed: RAV-1, RAV-2, RAV-5, RAV-6A, and RAV-7.

G.5.2. Verify that SMD external valves are in the following positions.

1. Open: SV-9.
2. Closed: SV-13, STV and FCV.

QA Witness: \_\_\_\_\_

**G.6. Check Initial pressure in Fill Line**

G.6.1. Install a pumping line between valve FCV on the Fill Cap Assembly and the Access Port #1 of the Auxiliary gas section.

G.6.2. Open AV-8.

G.6.3. Open AV-3.

G.6.4. Open valve FCV and evacuate to 20 mtorr as measured at AG-2.

G.6.5. Close AV-8 and FCV.

G.6.6. Once the pressure in the Fill Cap Assembly (PFCG) has stabilized, record Fill Cap Assembly pressure (PFCG): \_\_\_\_\_ torr.

G.6.7. Open valve SV-13 and bring the Fill Cap Assembly up to the pressure in the SMD fill line and record fill line pressure (PFCG): \_\_\_\_\_ torr.

QA Witness: \_\_\_\_\_

**G.7. Raise Pressure in Fill Line by opening RAV-1**

- G.7.1. Ensure all RAV controller selection switches in OFF position.
- G.7.2. Turn on RAV power supply and adjust current limit to 1.85 amps.
- G.7.3. Adjust power supply to 28 VDC.
- G.7.4. Power up controller #1.
- G.7.5. Position controller #1 selection switch to RAV-1.
- G.7.6. Record initial switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$
- G.7.7. Activate controller #1 to open RAV-1 and record:
1. Run time: \_\_\_\_\_ seconds
  2. Current draw: \_\_\_\_\_ amp
  3. Time of day: \_\_\_\_\_
- G.7.8. Record final switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$
- G.7.9. When convenient, record operation in RAV log book.

**NOTE****Do not power off controller.**

- G.7.10. Verify that the Fill Cap Assembly pressure (PFCG) rises to the Dewar Main Tank pressure EG-3 and record
1. Fill line pressure (PFC): \_\_\_\_\_ psig/torr.
  2. Main Tank Pressure (EG-3/STG) \_\_\_\_\_ torr.

QA Witness: \_\_\_\_\_

**G.8. Set up Data Acquisition****Note:** Refer to Operating Instructions for mechanics of DAS keyboard/mouse operations.

- G.8.1. Set Main Tank sampling interval to 1 minute.
- G.8.2. Set Guard Tank sampling interval to 1 minutes.

QA Witness: \_\_\_\_\_

**G.9. Prepare to Transfer**

G.9.1. Prepare RAV-2 for activation

1. Ensure controller #2 selection switch in OFF position.
2. Power up controller #2.
3. Position controller #2 selection switch to RAV-2.
4. Record initial switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$

G.9.2. Record Main Tank pressure (EG-3/STG): \_\_\_\_\_ torr.

G.9.3. Record Guard Tank pressure (EG-1a): \_\_\_\_\_ torr.

G.9.4. Record Main Tank pressure desired for initiating transfer \_\_\_\_\_ torr. **Note:** typically a value 15 torr greater than EG-1a is sufficient.

G.9.5. Record the desired final Guard Tank level: \_\_\_\_\_ %.

G.9.6. Input comment to DAS "Start Internal transfer to Guard Tank".

**CAUTION**

**This procedure necessitates closure of the Main Tank vent. During the period of closure the temperatures at station 200 and the top of the lead bag are to be continuously monitored.**

G.9.7. Close Main Tank vent as appropriate and record time: \_\_\_\_\_ .

---

 o Main Tank Vent Line Connected to Gas Module

1. Close EV-9

---

 o Main Tank Vent Line not connected to Gas Module

1. Close SV-9
- 

G.9.8. Enter comment in DAS, "Closed Main Tank Vent"

G.9.9. Turn on Tank Heater (H-8D or H-9D) power supply and adjust current limit to 1.25 amps.

G.9.10. Adjust power supply to 30 VDC and record:

V: \_\_\_\_\_ Vdc and I: \_\_\_\_\_ A

QA Witness: \_\_\_\_\_

**G.10. Initiate Transfer**

G.10.1. When the Main Tank pressure (EG-3/STG) reaches the desired initial pressure as noted in G.9.4, open RAV-2 and initiate transfer as follow

G.10.2. Close/Verify Closed EV-23

G.10.3. Activate controller #2 to open RAV-2 and record:

1. Run time: \_\_\_\_\_ seconds
2. Current draw: \_\_\_\_\_ amp
3. Time of day: \_\_\_\_\_

G.10.4. Record final switch status: Open: 0 0 Closed: 0 0

G.10.5. When convenient, record operation in RAV log book.

**Note**  
**Do not put RAV controller selection switches to OFF or power off RAV Controller.**

G.10.6. Open/Verify Open EV-13, EV-6, and EV-18 and record time:  
\_\_\_\_\_.

G.10.7. Record pressures:

1. EG-3/STG: \_\_\_\_\_ torr
2. EG-1a: \_\_\_\_\_ torr

G.10.8. Adjust Main Tank heater voltage, as necessary, to maintain desired transfer pressure, and record data in the following table.

Time	MT Pressure EG-3 (torr)	GT Pressure EG-1a (torr)	MT Heater Voltage (V)	MT LLS (%)	GT LLS (%)	Flow Rate PFM-1 (LL/hr)	Comments

--	--	--	--	--	--	--	--

QA Witness:\_\_\_\_\_

**G.11. Terminate Transfer to Guard Tank**

G.11.1. When the Guard Tank level reaches the value chosen in Paragraph G.9.5 Turn off Main Tank heater

G.11.2. Close RAV-2 as follows:

1. Verify controller #2 already powered up and controller #2 selection switch set to RAV-2. If not, perform the following steps:
2. Ensure controller #2 selection switch in off position
3. Power up controller #2.
4. Position controller #2 selection switch to RAV-2.
5. Record initial switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$
6. Activate controller #2 to close RAV-2 and record:
7. Run time:\_\_\_\_\_ seconds
8. Current draw:\_\_\_\_\_ amp
9. Time of day:\_\_\_\_\_
10. Record final switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$

G.11.3. Turn controller #2 selection switch to OFF.

G.11.4. Power off controller #2.

G.11.5. When convenient, record operation in RAV log book.

G.11.6. Close relief bypass valves EV-6 and EV-18.

G.11.7. Close EV-13 to isolate the Guard Tank and record:

1. Guard Tank Pressure (EG-1a): \_\_\_\_\_ torr
2. Main Tank pressure (EG-3/STG): \_\_\_\_\_ torr

G.11.8. Open Main Tank vent

---

o Main Tank Vent Line Connected to Gas Module

1. Open EV-9

---

o Main Tank Vent Line not connected to Gas Module

2. Open SV-9
-

## G.11.9. Establish Guard Tank Vent Configuration:

- 
- o Main Tank Vent Line Connected to Gas Module-Manifold Guard Tank and Main Tank Vent Paths
    1. Once Main Tank Pressure (EG-3) is within 3 torr of Guard Tank pressure (EG-1a), open EV-13  
Note: EV-6 may be opened for short periods to promote depressurization of Main Tank
    2. Close/Verify Closed EV-20
- 
- o Main Tank Vent Line not connected to Gas Module
    1. Open EV-13
    2. Close/Verify Closed EV-20
- 

G.11.10. Record flowrate EFM-1: \_\_\_\_\_.

G.11.11. Ensure EV-13 and EV-16 open.

G.11.12. If Main Tank Vent Line connected ensure EV-9 open

Once conditions have stabilized, record final transfer conditions:

- |                     |                  |         |
|---------------------|------------------|---------|
| 1. Main Tank level  | (LL-1D or LL-2D) | _____ % |
| 2. Guard Tank Level | (LL-5D or LL-6D) | _____ % |

QA Witness: \_\_\_\_\_

G.12. **Condition Dewar Fill Line and Fill Cap Assembly.**

- G.12.1. Ensure pumping line installed between Fill Cap Assembly at valve FCV and Auxiliary Gas Section access port no. 1.
- G.12.2. Ensure FCV closed.
- G.12.3. Close/verify closed AV-1 and AV-9.
- G.12.4. Open AV-8 and AV-3 and evacuate pumping line to <25 mtorr measured at AG-2b.



G.12.5. Close RAV-1 as follows :

**Note:**  
**Relief of the Dewar fill line will be through the relief valve in the Fill Cap Assembly until the next operation.**

1. Verify controller #1 already powered up and controller #1 selection switch set to RAV-1. If not, perform the following steps:
  2. Ensure controller #1 selection switch in off position
  3. Power up controller #1.
  4. Position controller #1 selection switch to RAV-1.
  5. Record initial switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$
  6. Activate controller #1 and record:
    - a. Run time: \_\_\_\_\_ seconds
    - b. Current draw: \_\_\_\_\_ amp
    - c. Time of day: \_\_\_\_\_
  7. Record final switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$
  8. Turn controller #1 selection switch to OFF.
  9. Power off controller #1.
  10. Turn off RAV power supply.
  11. When convenient, record operation in log book.
- G.12.6. Open FCV and evacuate Dewar fill line to < 25 mtorr as measured at AG-2b, and record AG-2b: \_\_\_\_\_ torr
- G.12.7. Close SV-13 and torque to 60 +/- 5 in-lbs.
- G.12.8. Close AV-8.
- G.12.9. Open AV-1
- G.12.10. Open AV-9 until pressure reaches 0.5 psig at AG-1, then close AV-9.
- G.12.11. Close AV-1 and AV-3.
- G.12.12. Close FCV.
- G.12.13. Turn off pump AP-1.
- G.12.14. Remove pumping line from Fill Cap Assembly.
- G.12.15. Install KF-25 blank-off cap on valve FCV and record:
1. PFCG pressure: \_\_\_\_\_
  2. Time of day: \_\_\_\_\_

G.12.16. Verify closure of SV-13 by observing the pressure in the Fill Cap Assembly (PFCG) until satisfied that no gas is leaking into the Dewar Fill line. After 30 minutes record:

Time of day: \_\_\_\_\_

PFCG pressure: \_\_\_\_\_

**Note:** If PFCG drops by more than 0.5 torr in 30 minutes, retorque SV-13 and repeat steps G.11.8 through G.11.16.

QA Witness: \_\_\_\_\_

### G.13. **Configure the DAS and Liquid Level Sensors**

G.13.1. Input comment to DAS “End of Internal transfer to Guard Tank”.

G.13.2. Set the DAS data cycle to 15 minutes.

G.13.3. Set all the liquid level sampling intervals to 10 minutes.

G.13.4. Ensure DAS alarm enabled and record set points if changed

o Thermal conditions substantially unchanged, alarm set points for Station 200 and lead bag unchanged

o Thermal conditions substantially changed, temperature alarm points reset as follows:

1. Station 200 set point [CN 1] \_\_\_\_\_ K ( $\leq 6.5$  K)

2. Top of Lead Bag set point [CN 28] \_\_\_\_\_ K ( $\leq 6.0$  K)

G.13.5. Ensure liquid level sensor alarms enabled and record set points if changed.

1. Main Tank Level Set Point \_\_\_\_\_%

2. Guard Tank Level Set Point \_\_\_\_\_%

### **CAUTION**

**The Guard Tank may tend to subcool following the completion of this procedure. Establish continuous monitoring of the Guard Tank pressure by placing it on the DAS alarm list. Maintain positive pressure in the Guard Tank by regulating the pressure through EV-23 when necessary**

G.13.6. Ensure Guard Tank pressure on DAS alarm list and set to alarm at 0.3 torr differential.

QA Witness: \_\_\_\_\_

**G.14. Verify Final Configuration**

G.14.1. Turn off Guard Tank vent-line heat exchanger (EH-2).

G.14.2. Verify final valve states

	Main Tank Vent Line Connected		Main Tank Vent Line Not Connected	
	Open	Closed	Open	Closed
<b>EV Valves</b>	EV-13, EV-9, EV-16, EV-7a/b	All other EV valves	EV-16, EV-13, EV-7a/b	All other EV-Valves
<b>AV Valves</b>	none	All	none	All

G.14.3. Confirm that all liquid level sensors are set at a sampling rate of 10 minutes.

G.14.4. Ensure that power to Vac-Ion pump is off.

G.14.5. Ensure RAV operations recorded in log book

1. RAV-1

2. RAV-2

G.14.6. Record Main Tank liquid usage:

a) Start level: \_\_\_\_\_ %, Finish level: \_\_\_\_\_ %.

b) Amount transferred: \_\_\_\_\_ liters (use 1 % = 24 l)

G.14.7. Verify Completion of Post Operations Checklist

QA Witness: \_\_\_\_\_

Completed by: \_\_\_\_\_

Witnessed by: \_\_\_\_\_

Date: \_\_\_\_\_

Time: \_\_\_\_\_

Quality Manager \_\_\_\_\_ Date \_\_\_\_\_

Payload Test Director \_\_\_\_\_ Date \_\_\_\_\_




Figure1. Schematic of Gas Module Plumbing.




Figure 2. Schematic of Pump Module plumbing.




Figure 3. Schematic of Science Mission Dewar plumbing.

## Appendix 1

DATE	CHECKLIST ITEM	COMPLETED	REMARKS
	1. Verify the test procedure being used is the latest revision.		
	2. Verify all critical items in the test are identified and discussed with the test team.		
	3. Verify all required materials and tools are available in the test area.		
	4. Verify all hazardous materials involved in the test are identified to the test team.		
	5. Verify all hazardous steps to be performed are identified to the test team.		
	6. Verify each team member knows their individual responsibilities.		
	7. CONFIRM THAT EACH TEST TEAM MEMBER CLEARLY UNDERSTANDS THAT HE/SHE HAS THE AUTHORITY TO STOP THE TEST IF AN ITEM IN THE PROCEDURE IS NOT CLEAR.		
	8. Confirm that each test team member clearly understands that he/she must stop the test if there is any anomaly or suspected anomaly.		
	9. NOTIFY MANAGEMENT OF ALL DISCREPANCY REPORTS OR D-LOG ITEMS IDENTIFIED DURING PROCEDURE PERFORMANCE. IN THE EVENT AN INCIDENT OR MAJOR DISCREPANCY OCCURS DURING PROCEDURE PERFORMANCE MANAGEMENT WILL BE NOTIFIED IMMEDIATELY.		
	10. Confirm that each test team member understands that there will be a post-test team meeting.		
	Team Lead Signature:		





Appendix 2

DATE	CHECKLIST ITEM	COMPLETED	REMARKS
	1. Verify all steps in the procedure were successfully completed.		
	2. Verify all anomalies discovered during testing are properly documented.		
	3. Ensure management has been notified of all major or minor discrepancies.		
	4. Ensure that all steps that were not required to be performed are properly identified.		
	5. If applicable sign-off test completion.		
	6. Verify all RAV valve operations have been entered in log book		
	7. Verify the as-run copy of procedure has been filed in the appropriate binder		
	Team Lead Signature:		

## Appendix 3– Contingency Responses

	Condition	Circumstance	Response
1	Temperature limits (CN 1 or 28) exceeded	Main tank is not venting	<p>ALLOW MAIN TANK TO VENT</p> <p>If SV-9 is closed:</p> <p><b>Close EV-17 (if open) and verify EV-9 open, crack open SV-9 to allow MT to vent. Adjust SV-9 as necessary to restore temperature(s) below alarm limits. Open EV-6 and EV-18 if higher flow rate is needed.</b></p> <p>If SV-9 open and EV-9 closed:</p> <p><b>Open EV-9 for short periods (~15 sec) and allow increased flow from Main tank; in addition, Open EV-6 and EV-18 if higher flow rate is needed.</b></p> <p>If SV-9 and EV-9 open</p> <p><b>Open EV-6 and EV-18 for higher flow</b></p> <p><b>If problem persists see item 3</b></p>
2		Main tank is venting	<p>PROMOTE INCREASE IN MAIN TANK VENTING</p> <p>Power up heater at H08D or H0-9D and starting at 15 vdc input increase power until increased flow has cooled the problem area</p>
3	Burst disk rupture (MT/GT)	Any time	Evacuate room