GRAVITY PROBE B PROCEDURE FOR SCIENCE MISSION DEWAR

Pump-out Probe with Vacuum Module

TIMO DOCATORIOS	OCALT ALLIC		ADED ATIONS
THIS PROCEDURE	CONTAINS	HAZAKDOUS	OPERATIONS

P0966 January 6, 2003

Written by			
,	Date		
Ned Calder Cryogenic Test			
Approvals:			
	Date		Date
Dorrene Ross		Harv Moskowitz	
Quality Assurance		LMMS Safety	
	Date		Date
Rob Brumley		Mike Taber	
Payload Technical Ma	nager	Payload Test Director	

REVISION RECORD

REV	ECO	PAGES	DATE
-	-		-

Table of Contents

A.	SCO	PE	1
B.	SAFE	ETY	1
	B.1.	Potential Hazards	
	B.2.	Mitigation of Hazards	
	B.3.	Mishap Notification	
C.	QUAI	LITY ASSURANCE	
	C.1.	QA Notification	2
	C.2.	Red-line Authority	2
	C.3.	Discrepancies	2
D.	TEST	FPERSONNEL	3
	D.1.	Personnel Responsibilities	3
	D.2.	Personnel Qualifications	
	D.3.	Qualified Personnel	3
E.	REQI	UIREMENTS	3
	E.1.	Electrostatic Discharge Requirements	3
	E.2.	Lifting Operation Requirements	
	E.3.	Hardware/Software Requirements	
	E.4.	Instrument Pretest Requirements	5
	E.5.	Configuration Requirements	6
	E.6.	Optional Non-flight Configurations	6
F.	REFE	ERENCE DOCUMENTS	7
	F.1.	Drawings	7
	F.2.	Supporting documentation	7
	F.3.	Additional Procedures	7
G.	OPE	RATIONS	8
	G.1.	Verify Preparations	8
	G.2.	Initial Operations	8
	G.3.	Verify Configuration Requirements	8
	G.4.	Prepare/ Verify Prepared HEPA Down Flow Booth	9
	G.5.	Verify Vacuum Module State (Figure 2)	9
	G.6.	Verify Leakage Valve State	
	G.7.	Install Vatterfly Adapter Flange and Connect Vacuum Module	10
	G.8.	Leak Check All Conections	11
	G.9.	Initiate Pumping on the Probe	11
	G.10.	Establish Final Configuration	12

List of Abbreviations and Acronyms

AG-x	Gauge x of Gas Module auxiliary section	MT	Main Tank
AMI ATC	American Magnetics Inc. Advanced Technology Center	MTVC MTVC-G	Main Tank Vent Cap Main Tank Vent Cap pressure gauge
Aux AV-x Bot CN [xx] DAS	Auxiliary Valve x of Gas Module auxiliary section Bottom Data acquisition channel number Data Acquisition System	MTVC-RV MTVC-V NBP ONR PFCG	Main Tank Vent Cap relief valve Main Tank Vent Cap valve Normal boiling point Office of Naval Research Fill Cap assembly pressure Gauge
EFM EG-x	Exhaust gas Flow Meter Gauge x of Gas Module exhaust section	PFM PG-x	Pump equipment Flow Meter Gauge x of Pump equipment
EM ERV-x	Electrical Module Relief valve of Gas Module exhaust section	PM psi	Pump Module pounds per square inch
EV-x	Valve number x of Gas Module exhaust section	psig	pounds per square inch gauge
FCV FIST GHe GM GP-B GSE GT GTVC-G GTVC-RV GTV-V GTV-V HX-x KFxx LHe LHSD Liq	Fill Cap Valve Full Integrated System Test Gaseous Helium Gas Module Gravity Probe-B Ground Support Equipment Guard Tank Guard Tank Vent Cap Guard Tank Vent Cap pressure gauge Guard Tank Vent Cap relief valve Guard Tank Vent Cap relief valve Guard Tank Vent Cap valve Guard Tank vent pressure gauge Guard Tank vent pressure gauge Guard Tank vent relief valve Guard Tank vent valve Vent line heat exchanger in Gas Module Quick connect o-ring vacuum flange (xx mm diameter) Liquid Helium Liquid Helium Supply Dewar Liquid	PTD PV-x QA RAV-x RGA SMD STV SU SV-x TG-x TV-x UTS Vac VCP-x VCRV-x VCRV-x VDC VF-x VG-x	Payload Test Director Valve x of the Pump equipment Quality Assurance Remote Actuated Valve-x Residual Gas Analyzer Science Mission Dewar SMD Thruster vent Valve Stanford University SMD Valve number x Gauge x of Utility Turbo System Valve x of Utility Turbo System Utility Turbo System Vacuum Vent cap pressure gauge Vent cap relief valve Vent cap valve Volts Direct Current Liquid helium Fill line valve Gauge x of Vacuum Module
LL LLS LMMS LMSC	Liquid level Liquid level sensor Lockheed Martin Missiles and Space Lockheed Missiles and Space Co.	VM VV-x VW-x	Vacuum Module Valve x of Vacuum Module Valve x of Dewar Adapter

A. SCOPE

This procedure describes the steps necessary to connect the Vacuum Module to one of the Probe LV valves and initiates pumping on the Probe. The steps include

- -Perform leak back test to ensure LV-1/2 closed
- -Connect Pumping line and associated plumbing
- -Leak check all connections
- -Open LV-1/2 and statically measure the Probe pressure
- -Begin actively pumping Probe with Vacuum Module

Note that to discontinue pumping requires performing procedure P0967

B. SAFETY

B.1. Potential Hazards

Personal injury and hardware damage can result during normal positioning, assembly and disassembly of hardware. Examples include: positioning Dewar in tilt stand; integrating probe with airlock; positioning airlock on Dewar; removing airlock from Dewar; removing probe from Dewar; and positioning support equipment such as pressurized gas cylinders and supply dewars.

A number of undesired events may be associated with these operations. For example, personnel or equipment can be struck when hardware is being moved (e.g. by forklift or crane load). Personnel are subject to entrapment while positioning hardware, such as hands or feet caught between objects as hardware is moved into place. Suspended hardware may be dropped. Personnel can be caught between objects such as forklifts and walls or loads and building support columns.

In addition, liquid helium used in the SMD represents a hazardous material for the personnel involved in the operations. Cryogenic burns can be caused by contact with the cold liquid or gas, high pressures can result if boiling liquid or cold gas is confined without a vent path, and asphyxiation can result if the vent gas is allowed to accumulate.

The SMD Safety Compliance Assessment, document GPB-100153C discusses the safety design, operating requirements and the hazard analysis of the SMD.

B.2. Mitigation of Hazards

B.2.1. Lifting hazards

There are no lifting operations in this procedure.

B.2.2. Cryogenic Hazards

The LM Building may have an oxygen deficiency monitor that alarms when the oxygen level is reduced to 19.5%. Additional temperature and pressure alarms, provided by the DAS, warn of potential over-pressure conditions. Emergency vent line deflectors are installed over the four burst disks on the SMD vacuum shell.

Only authorized and trained LM and SU personnel are allowed In the LM facilities without escort. All personnel working at a height 30 inches or more off the floor are required to have an LM-approved Emergency Breathing Apparatus (EEBA) within easy reach. In the unlikely event of a

large LHe spill all employees have been instructed to evacuate the room and contact LM safety.

The following requirements apply to personnel involved in cryogenic operations. Gloves that are impervious to liquid helium and liquid nitrogen are to be worn whenever the possibility of splashing or impingement of high-velocity cryogens exists or when handling equipment that has been cooled to cryogenic temperatures. Protective clothing and full-face shields are to be worn whenever the possibility of splashing cryogens exists.

B.2.3. Other Hazards

When appropriate, tools or other items used with the potential to damage the SMD or Probe shall be tethered.

B.3. Mishap Notification

B.3.1. Injury

In case of any injury obtain medical treatment as follows LM Call 117

B.3.2. Hardware Mishap

In case of an accident, incident, or mishap, notification is to proceed per the procedures outlined in Lockheed Martin Engineering Memorandum EM SYS229.

B.3.3. Contingency Response

Responses to contingencies (e.g., power failure) are listed in Appendix 3.

C. QUALITY ASSURANCE

C.1. QA Notification

The NASA representative and SU QA shall be notified 24 hours prior to the start of this procedure. Upon completion of this procedure, the QE Manager will certify his/her concurrence that the effort was performed and accomplished in accordance with the prescribed instructions by signing and dating in the designated place(s) in this document.

C.2. Red-line Authority

Authority to red-line (make minor changes during execution) this procedure is given solely to the Test Director or his designate and shall be approved by the QA Representative. Additionally, approval by the Hardware Manager shall be required, if in the judgement of the Test Director or QA Representative, experiment functionality may be affected.

C.3. Discrepancies

A Quality Assurance Representative designated by D. Ross shall review any discrepancy noted during this procedure, and approve its disposition. Discrepancies will be recorded in a D-log or a DR per Quality Plan P0108. Any time a procedure calls for verification of a specific configuration and that configuration is not the current configuration, it represents a discrepancy of one of three types. These types are to be dealt with as described below.

- 1. If the discrepancy has minimal effect on procedure functionality (such as the state of a valve that is irrelevant to performance of the procedure) it shall be documented in the procedure, together with the resolution. Redlines to procedures are included in this category.
- 2. If the discrepancy is minor and affects procedure functionality but not flight hardware fit or function, it shall be recorded in the D-log. Resolution shall be in consultation with the TD and approved by the QA representative.
- 3. All critical and major discrepancies, those that effect flight hardware fit or functions, shall be documented in a D-log and also in a Discrepancy Report, per P0108.

D. TEST PERSONNEL

D.1. Personnel Responsibilities

The performance of this procedure requires a minimum complement of personnel as determined by the Test Director. The person performing the operations (Test Director or Test Engineer) is to sign the "Completed by" sign-off. Any other qualified person or QA person who can attest to the successful performance of this procedure may sign the "Witnessed by" sign-off. The Test Director will perform pre-test and Post-Test briefings in accordance with P0875 "GP-B Maintenance and Testing at all Facilities". Checklists will be used as directed by P0875.

D.2. Personnel Qualifications

The Test Director must have a detailed understanding of all procedures and facility operations and experience in all of the SMD operations. Test Engineers must have SMD Cryogenic operations experience and an understanding of the operations and procedures used for the cryogenic servicing/maintenance of the Dewar.

D.3. Qualified Personnel

The names of those actually performing this procedure are to be initialed and the name of the person acting as Test Director should be circled.

Test Director	Test Engineer
Ned Calder	Tom Welsh
Mike Taber	
Dave Murray	

E. REQUIREMENTS

E.1. Electrostatic Discharge Requirements

When working on the space vehicle, proper ESD grounding is required

E.2. Lifting Operation Requirements

There are no lifting operations in this procedure

E.3. Hardware/Software Requirements

E.3.1. Commercial Test Equipment

Description
Varian Leak Detector
Model #
Cal Due Date:
Met One model Particle Counter

E.3.2. Ground Support Equipment

The Ground Support Equipment includes the Gas Module, the Pump Module, the Electrical Module, and the Vacuum Module. The Gas Module provides the capability to configure vent paths, read pressures and flow rates, and pump and backfill vent lines. The Pump Module provides greater pumping capacity than the Gas Module, together with additional flow metering capabilities. The vent output of the Gas Module flows through the Pump Module. The Electrical Module contains the instruments listed in Table 1, and provides remote control of valves in the Gas Module, Pump Module, and SMD. The Vacuum Module contains a turbo pump, backed by a vane pump, and provides the capability to pump out the SMD vacuum shell.

This procedure calls for use of hardware located in the Electrical Module (Table 1),as well as the Vacuum Module.

E.3.3. Computers and Software:

The Data Acquisition System (DAS) and data acquisition software are required for this procedure. The DAS reads and displays pressures, temperatures, and flow rates and monitors critical parameters. No additional computers or software are required.

E.3.4. Additional Test Equipment

Description			

E.3.5. Additional Hardware

	Description
2" dia. Stainless steel flex line	

E.3.6. Tools

Description				

E.3.7. Expendables

Description	Quantity	Mfr./Part No.
Alcohol	AR	N/A
99.999% pure gaseous helium	AR	N/A
Vacuum Grease	AR	Dow Corning High Vacuum or Apiezon N

E.4. Instrument Pretest Requirements

The GSE instruments required to perform this procedure are listed in Table 1, together with their serial numbers, where available. Instruments that are required to have current calibrations are indicated in the Cal-Required column. Instruments that do not require calibration are those not used to verify performance requirements and are not connected to flight instrumentation. The status column is to be filled in with the due date of the instrument calibration sticker and verified to be in calibration by QE or QE designee.

Table 1. Required Instrumentation and Calibration Status

No.	Location	Description	User Name	Serial No.	Cal Required	Status Cal due date
1	DAS	Power Supply, H-P 6627A	-	3452A01975	Yes	
2	DAS	Power Supply, H-P 6627A	-	3452A01956	Yes	
3	DAS	Data Acquisition/Control Unit H-P 3497A	-	2936A245539	No	-
4	DAS	Digital Multimeter H-P 3458A	-	2823A15047	Yes	
5	EM	Vacuum Gauge Controller Granville-Phillips Model 316	EG-1a, -1b	2827	No	-
6	EM	Vacuum Gauge Controller Granville-Phillips Model 316	AG-2a, -2b	2826	No	-
7	EM	Vacuum Gauge Controller Granville-Phillips Model 316	EG-3	2828	No	-
8	EM	MKS PDR-C-2C	EG-2, FCG	92022108A	No	-
9	EM	Flow meter – Matheson 8170	EFM-1	96186	No	-
10	EM	Flow meter totalizer Matheson 8124	EFM-1	96174	No	-
11	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Main Tank	96-409-11	No	-
12	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Guard Tank	96-409-10	No	-
13	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Well	96-409-9	No	-
14	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Axial Lock	96-409-12	No	-
15	EM	Pressure Controller – MKS 152F-92	EV-7a, -7b	96203410A	No	-
16	EM	Power Supply HP 6038A	H08D Tank Heater	96023407A	Yes	
17	EM	Power Supply HP 6038A	H09D Tank Heater	3511A-13332	Yes	
18	EM	Power Supply HP 6038A	RAV Power Supply	3329A-12486	Yes	
19	EM	Vac Ion Pump power supply Varian 929-0910, Minivac	SIP	5004N	No	-
20	EM	Flow meter totalizer Veeder-Root	PFM-1	576013-716	No	-
21	GM	Pressure Gauge, Heise	AG-1	CC-122077	No	-
22	GM	Pressure Gauge, Marshall Town	AG-3	N/A	No	-

No.	Location	Description	User Name	Serial No.	Cal Required	Status Cal due date
23	GM	Main Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller	-	C-19950	No	1
24	GM	Guard Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller	-	C-09920	No	1
25	VM	Vacuum Gauge readout, Granville-Phillips 316	VG-3 VG-4	2878	No	1
26	VM	Vacuum Gauge readout, Granville-Phillips 360	VG-1, VG-2 VG-5	96021521	No	-

E.5. Configuration Requirements

E.5.1. Space Vehicle

The Space Vehicle is mounted in the tilt dolly and in the horizontal orientation.

E.5.2. Main Tank

Liquid in the Main Tank may be either subatmospheric or at NBP.

E.5.3. Guard Tank

The Guard Tank is depleted of liquid.

E.5.4. Well

There are no requirements on the Well.

E.5.5. SMD Vacuum Shell

There is no requirement on the vacuum shell pressure.

E.5.6. Alarm System

- 1. The DAS alarm system must be enabled and contain the following alarm set-points:
 - a. Top of lead bag temperature set (CN 175) at T \leq 6.0 K.
 - b. Top of lead bag temperature set (CN 178) at $T \le 6.0$ K.
 - c. Relative Guard Tank Pressure (CN 46) set at $\Delta P \ge 30$ torr.
- 2. The Watch Dog alarm must be armed.

E.5.7. GSE and Non-flight Hardware

1. GSE cabling must be connected between the SMD and the Electrical Module (P/N 5833812) and between the SMD and the Data Acquisition System (P/N 5833811).

E.6. Optional Non-flight Configurations

The following modifications or non-flight arrangement of the basic SMD configuration may also be in place. They are incidental to the performance of this procedure and not required.

1.

- 2. The ion-pump magnet is installed.
- 3. The Main Tank vent line may be connected to the Gas Module or disconnected with a vent cap installed.
- 4. The Guard Tank vent line may be connected to the Gas Module or disconnected with a vent cap installed.

5.

- 6. The thruster vent port is flanged to a shut-off valve.
- 7. The Fill Cap Assembly is installed at SV-13 (See Figure 1)

F. REFERENCE DOCUMENTS

F.1.Drawings

Drawing No.	Title
LMMS-5833394	Instrumentation Installation

F.2.Supporting documentation

Document No.	Title
LMMC-5835031	GP-B Magnetic Control Plan
GPB-100153C	SMD Safety Compliance Assessment
SU/GP-B P0141	FIST Emergency Procedures
LMSC-P088357	Science Mission Dewar Critical Design Review
SU/GP-B P0108	Quality Plan
LMMS GPB-100333	Science Mission Dewar Failure Effects and Causes Analysis
EM SYS229	Accident/Mishap/Incident Notification Process
SU/GP-B P0875	GP-B Maintenance and Testing at all Facilities
SU/GP-B P0879	Accident/ Incident/Mishap Notification Process
SU/GP-B P059	GP-B Contamination Control Plan

F.3.Additional Procedures

N/A

Document No.	Title

		Operation Number:
		Date Initiated:
		Time Initiated:
G.	OPER	ATIONS
	G.1.	Verify Preparations
		G.1.1. Verify SU QA notified. Record: Individual notified, Date/time/
		G.1.2. Verify NASA representative notified. Record: Individual notified
		G.1.3. Verify that persons actually performing this procedure have initialed their names in Sec. D.3 and the name of the Test Director is circled.
		G.1.4. Verify completion of pre-operations checklist
		G.1.5. Ensure Space Craft powered up and prepared to operate Vatterfly valve and read P9 gauge.
		Section Complete Quality
	G.2.	Initial Operations
		G.2.1. Record serial number on helium bottle/s to be tested. 1 2 3 4 5 6
		G.2.2. Verify Helium cylinder content has been tested and record operation number. Opt Number:
		QA Witnesss:
	G.3.	Verify Configuration Requirements
		G.3.1. Ensure Watch Dog Timer enabled.
		G.3.2. Verify DAS alarm system enabled and record set points. 1. <i>Top of lead bag temperature</i> – verify CN [175] on DAS alarm list and set to alarm at T ≤ 6.0 K. Record set point. K
		 Top of lead bag temperature – verify CN [178] on DAS alarm list and set to alarm at T ≤ 6.0 K. Record set point.

		 3. Relative Guard Tank Pressure – verify CN [46] on DAS alarm list and set to alarm at ΔP ≥ 30 torr. Record set point. torr
	G.3.3.	 Verify liquid-level alarms set, as appropriate, and record set points. 1. <i>Main Tank</i> – verify liquid-level alarm set ≥20%. Record set point% 2.
		Section Complete Quality
G.4.	Prepa	re/ Verify Prepared HEPA Down Flow Booth
	G.4.1.	Ensure HEPA down flow booth installed over Vatterfly Valve and has been running for at least 30 minutes
	G.4.2.	Using particle counter ensure Class 10 environment 1. Record Particle Counter S/N#: and Cal Due Date:
		2. Record particle count:
G.5.	Vorify	QA Witness: Vacuum Module State (Figure 2)
G.5.	-	, • <i>,</i>
	G.5.1.	Ensure Vacuum Module Certified since last major move or modification 1. Record Opt Number:
	G.5.2.	Ensure all valves closed1. VV-1, VV-2, VV-3, VV-4, VV-5, VV-6, VV-7, VV-10, VV-11, VV-RGA
	G.5.3.	Ensure all access ports capped 1. Access port at VV-7 2. Access port at VV-2 3. ISO 100 access port at Main Pump Inlet 4. Ensure RGA head installed at VV-RGA QA Witness:
G.6.	Verify	Leakage Valve State
	G.6.1.	Record Vatterfly Valve to be connected to:
		Note:
		LV-1 located in –X, –Y quadrant LV-2 located in –X, +Y quadrant
	G.6.2.	Record Vatterfly valve cover gauge:torr
		Verify the cover is evacuated
Section G.6.3	performs	Note: a leak back test of the Vatterfly valve to ensure that it is closed before the

cover is removed.

G.6.3. Connect Vacuum Module to Vatterfly Cover Valve

- Connect pumping line between Vatterfly Cover Valve (VC-V) and VV-10 of Vacuum Module
- 2. Turn on VP-2
- 3. Turn Vacuum Module Override Switch to On position (up)
- 4. Open VV-4, VV-3, VV-6 and VV-10
- 5. When VG-3 reads <50 mtorr, open VC-V
- 6. When VG-3 reads <50 mtorr, close VV-4 and VV-10
- 7. Connect certified helium source to VV-7 set at ~1 psig
- 8. Open VV-7 and then close VV-7
- 9. Open VV-4
- 10. Close VV-4 when VG-3 reads <50 mtorr
- 11. Open VV-10
- 12. Open VV-7 and backfill cover until VG-4 reads 10 torr and then close VV-7.
- 13. Record VG-4:
- 14. After half hour, record VG-4:
- 15. Verify no decrease in pressure
- Open VV-7 and backfill to 760 torr as read on VG-4, then close VV-
- 17. Close VC-V
- 18. Close VV-10
- 19. Open VV-4
- 20. When VG-3 reads 50 mtorr close VV-4, VV-3 and VV-6

()A Withess.	$\cap \Delta$	Witness:	
--------------	---------------	----------	--

G.7. Install Vatterfly Adapter Flange and Connect Vacuum Module

- G.7.1. Verify Vatterfly Adapter Flange has been doubled bagged
- G.7.2. Ensure the 10' x 2" dia. pumping line has been cleaned for vacuum
- G.7.3. Ensure the individual/s working under the HEPA down flow booth where clean room suit, gloves and hood.
- G.7.4. Remove the ISO 200 protective closeout from the Vatterfly valve and double bag for future use.
- G.7.5. Unbag and install the Vatterfly Adapter Flange using stainless steel or silver-plated bolts (non-cadmium) and existing ISO hardware

Note:

Nominal torque value for NW-50 EVAC Al seals with their associated chain clamps is 44 in-lbs, although increasing this value is often necessary.

- G.7.6. Connect pumping line to KF-50 fitting on Adapter Flange using an EVAC Al seal
- G.7.7. Connect Probe Pump-out Manifold (see figure 2) to VV-10 of Vacuum Module using EVAC Al seals

	G.7.8.	Connect pumping line to input of Probe Pump-out Manifold using EVAC Al seal
		QA Witness:
G.8.	Leak	Check All Conections
	G.8.1.	Ensure on VP-2
	G.8.2.	Open VV-4, VV-3, VV-6, VV-10
	G.8.3.	When VG-3 reads approximately 100 mtorr, press start on Turbo Controller
	G.8.4.	When Turbo at full speed (green power light comes on solid), close VV-6 and VV-3
	G.8.5.	Open VV-1
	G.8.6.	Turn on ionization gauge VG-1
	G.8.7.	Connect Leak Detector to VV-7 Access Port
		Leak Check all joints between Vacuum Module/ leak detector and Probe 1. Calibrate Leak Detector a. Calibrated Leak:sccs b. Measure Leak:sccs c. Verify measured leak rate within 2% of calibrated leak rate. 2. Leak check all joints between leak detector and Vacuum Module 3. Slowly open VV-7 4. Close VV-4 5. Ensure leak detector background on the E-7 scc/s He range 6. Spray helium around all joints between Vacuum Module and Probe a. Record initial leak rate:sccs b. Record final leak rate:sccs c. Verify no rise detected 7. Open VV-4 8. Close VV-7 9. While monitoring VG-1, vent and disconnect leak detector 10. Cap port at VV-7 QA Witness:
G.9.	Initiat	e Pumping on the Probe
	G.9.1.	Verify VG-1 is < 5. E-5 torr
	G.9.2.	Place Vacuum Module Override switch in off position (down).
	G.9.3.	Close VV-1
	G.9.4.	Record P-9 gauge:torr, counts:
	G.9.5.	Record VG-1:torr
	G.9.6.	Request LM Space Vehicle Team open Vatterfly valve 1. Record date and time:/

	2. G.9.8. Fill L	<u> </u>	ton		
		<u> </u>			
	The L.N.		Note:		
	The LN ₂ trap will last for \sim 24 hours when under vacuum.				
	G.9.9. Ope	n VV-1			
	G.9.10. (Option) Set-up RGA				
	Slowly open VV-RGA				
	2.	рего размения по			
	3.	Start up program	-	vare	
	4. 5.	Record Recipe: Record file nam			
				na Probe with \	/acuum Module."
	•	re VG-1 recordir	•	_	acuum Module.
		n recording data			na chart:
Doto/Time	VG-1 (torr)		P-9	LN2 Fill	
Date/Time	VG-1 (toll)	VG-2 (torr)	P-9	LINZ FIII	Comments
			Section	n Complete C	Quality
G.10.	Fetablieb F	inal Configuration	n .		

G.9.7. After telemetry indicates Vatterfly valve fully open

G.10.2. Ensure Vacuum Module override switch set on off (down) position

G.10.1. Ensure VG-1 alarm set at <5*E-5 torr on the DAS

- G.10.3. Ensure all potential trip hazards clearly labeled or mitigated (power cords, pumping lines with signs, etc.)
- G.10.4. Ensure Watch Dog Timer is armed.
- G.10.5. Perform Post-Operations Checklist (Appendix 2)

Note:		
To discontinue pumping of the Probe with the Va	ncuum Module, perfor	m procedure P0967.
	Section Complete	Quality
Completed by:		
Date:		
Time:		
Quality Manager	Da	te
Payload Test Director	Dat	te




Figure 1. Schematic of Science Mission Dewar plumbing.




Figure 2. Schematic diagram of Vacuum Module

Appendix 1

	Appena	IX I			
DATE	CHECKLIST ITEM	COMPLETED	REMARKS		
	Verify the test procedure being used is the latest revision.				
	Verify all critical items in the test are identified and discussed with the test team.				
	3. Verify all required materials and tools are available in the test area.				
	4. Verify all hazardous materials involved in the test are identified to the test team.				
	5. Verify all hazardous steps to be performed are identified to the test team.				
	6. Verify each team member knows their individual responsibilities.				
	7. Confirm that each test team member clearly understands that he/she has the authority to stop the test if an item in the procedure is not clear.				
	8. Confirm that each test team member clearly understands that he/she must stop the test if there is any anomaly or suspected anomaly.				
	9. Notify management of all discrepancy reports or d-log items identified during procedure performance. In the event an incident or major discrepancy occurs during procedure performance management will be notified immediately.				
	Confirm that each test team member understands that there will be a post-test team meeting. Team Lead Signature:				
	3				

Appendix 2

	Appendix 2					
DATE	CHECKLIST ITEM	COMPLETED	REMARKS			
	4 37 76 11 1 1 1					
	1. Verify all steps in the procedure					
	were successfully completed.					
	2. Verify all anomalies discovered					
	during testing are properly					
	documented.					
	3. Ensure management has been					
	notified of all major or minor					
	discrepancies.					
	4. Ensure that all steps that were					
	not required to be performed are					
	properly identified.					
	property identificati					
	5. If applicable sign-off test					
	5. Il applicable signi-on test					
	completion.					
	6. Verify all RAV valve operations					
	have been entered in log book					
	7. Verify the as-run copy of					
	procedure has been filed in the					
	appropriate binder					
	T					
	Team Lead Signature:					

Appendix 3– Contingency Responses

	Condition	Circumstance	Response
1	Burst disk rupture (MT/GT)	Any time	Evacuate room