

GRAVITY PROBE B PROCEDURE FOR SCIENCE MISSION DEWAR

Configure SMD for Transport to SLC-2W

To be performed at Vandenberg Air Force Base building 1610

THIS DOCUMENT DOES NOT CONTAIN HAZARDOUS OPERATIONS

P1002 Rev A

ECO No. 1444

September 17, 2003

Prepared by

Checked by

_____ Date _____

_____ Date _____

Mike Taber
Cryogenic Test

Dave Murray
Cryogenic Test

Approvals:

_____ Date _____

_____ Date _____

Dorrene Ross
Quality Assurance

Harv Moskowitz
LM Safety

_____ Date _____

_____ Date _____

Robert Brumley
Payload Technical Manager

For VAFB Safety

Revision Record

| <i>Rev</i> | <i>ECO</i> | <i>Revisions</i> | <i>Date</i> |
|-------------------|-------------------|--|--------------------|
| A | 1444 | Changed liquid He requirement from 200 to 500 liters Updated procedure references Reordered sequence in section G Added table to record GT fill operations Added requirement that the PTD observe the critical operation of RAV-3 closure and verify the opening of SV-12 Changed securing of SV-12 from safety wire to epoxy stake Call for disconnecting vacuum and vent lines prior to SV rotation for solar array installation | |

Table of Contents

| | | |
|----|---|-------------------------------------|
| A. | Scope..... | 1 |
| B. | Safety..... | 1 |
| | B.1. Potential Hazards..... | 1 |
| | B.2. Mitigation of Hazards..... | 2 |
| | B.3. Mishap Notification..... | 2 |
| C. | Quality Assurance..... | 3 |
| | C.1. QA Notification..... | 3 |
| | C.2. Red-line Authority..... | 3 |
| | C.3. Discrepancies..... | 3 |
| D. | Test Personnel..... | 4 |
| | D.1. Personnel Responsibilities..... | 4 |
| | D.2. Personnel Qualifications..... | 4 |
| | D.3. Qualified Personnel..... | Error! Bookmark not defined. |
| E. | Requirements..... | 4 |
| | E.1. Electrostatic Discharge Requirements..... | 4 |
| | E.2. Lifting Operation Requirements..... | 4 |
| | E.3. Hardware/Software Requirements..... | 4 |
| | E.4. Instrument Pretest Requirements..... | 6 |
| | E.5. Configuration Requirements..... | 8 |
| | E.6. Optional Non-flight Configurations..... | 9 |
| | E.7. Verification/Success Criteria..... | 9 |
| | E.8. Payload Constraints and Restrictions..... | 9 |
| F. | Reference Documents..... | 9 |
| | F.1. Drawings..... | 9 |
| | F.2. Supporting documentation..... | 9 |
| | F.3. Additional Procedures..... | 9 |
| G. | Operations..... | 11 |
| | G.1. Pre-Operations Verifications..... | 11 |
| | G.2. Verify Preliminary SMD and GSE Preparations Complete..... | 11 |
| | G.3. Verify Configuration Requirements..... | 11 |
| | G.4. Guard Tank Fill Operations..... | 13 |
| | G.5. Closeout of the Main Tank..... | 13 |
| | G.6. Additional Preparations for FEE Closure..... | 14 |
| | G.7. Closure of RAV-6B..... | 15 |
| | G.8. Steps To Be Performed to Allow SV Rotation for Solar Array Installation..... | 15 |
| | G.9. Steps To Be Performed Prior to Enclosure for Transport to MST..... | 15 |
| H. | Procedure Completion..... | 16 |
| I. | Appendix 1 – Pre-Procedure Checklist..... | 20 |
| J. | Appendix 2 – Post-Procedure Checklist..... | 21 |
| K. | Appendix 3– Contingency Responses..... | 22 |

List of Abbreviations and Acronyms

| | | | |
|---------|---|---------|-----------------------------------|
| AG-x | Gauge x of Gas Module auxiliary section | MT | Main Tank |
| AMI | American Magnetics Inc. | MTVC | Main Tank Vent Cap |
| APR-x | Pressure regulator x of Gas Module | MTVC-G | Main Tank Vent Cap pressure gauge |
| AV-x | Valve x of Gas Module auxiliary section | MTVC-RV | Main Tank Vent Cap relief valve |
| CG-x | Gauge x of portable helium pressurization source | MTVC-V | Main Tank Vent Cap valve |
| CPR-x | Pressure regulator x of portable helium pressurization source | NBP | Normal boiling point |
| CV-x | Valve x of portable helium pressurization source | PAF | Payload Adapter Flange |
| CN [xx] | Data acquisition channel number | PFCG | Fill Cap ass'y pressure Gauge |
| DAS | Data Acquisition System | PFM | Pump equipment Flow Meter |
| EFM | Exhaust gas Flow Meter | PG-x | Gauge x of Pump equipment |
| EG-x | Gauge x of Gas Module exhaust section | PM | Pump Module |
| EH-x | Vent line heat exchanger in Gas Module | psi | pounds per square inch |
| EM | Electrical Module | psig | pounds per square inch gauge |
| ERV-x | Relief valve of Gas Module exhaust section | PV-x | Valve x of the Pump equipment |
| EV-x | Valve number x of Gas Module exhaust section | QA | Quality Assurance |
| FCV | Fill Cap Valve | RAV-x | Remote Actuated Valve-x |
| FEE | Forward Equipment Enclosure | RGA | Residual Gas Analyzer |
| GHe | Gaseous Helium | SMD | Science Mission Dewar |
| GM | Gas Module | STG | SMD Thruster vent pressure gauge |
| GP-B | Gravity Probe-B | SU | Stanford University |
| GSE | Ground Support Equipment | SV | Space Vehicle |
| GT | Guard Tank | SV-x | SMD Valve number x |
| GTVC | Guard Tank Vent Cap | TD | Test Director |
| GTVC-G | Guard Tank Vent Cap pressure gauge | TG-x | Gauge x of Utility Turbo System |
| GTVC-RV | Guard Tank Vent Cap relief valve | TV-x | Valve x of Utility Turbo System |
| GTVC-V | Guard Tank Vent Cap valve | UTS | Utility Turbopump System |
| GTV-G | Guard Tank vent pressure gauge | Vac | Vacuum |
| GTV-RV | Guard Tank vent relief valve | VCP-x | Vent cap pressure gauge |
| GTV-V | Guard Tank vent valve | VCRV-x | Vent cap relief valve |
| KFxx | Quick connect o-ring vacuum flange (xx mm diameter) | VCV-x | Vent cap valve |
| LHe | Liquid Helium | VDC | Volts Direct Current |
| LHSD | Liquid Helium Supply Dewar | VF-x | Liquid helium Fill line valve |
| LHV-x | Liquid Helium Supply Dewar valves | VG-x | Gauge x of Vacuum Module |
| LLS | Liquid level sensor | VM | Vacuum Module |
| LM | Lockheed Martin Co. | VV-x | Valve x of Vacuum Module |
| MOC | Mission Operations Center | VW-x | Valve x of Dewar Adapter |

LIST OF SPECIFIC HEADING DEFINITIONS

Each type of alert message will precede the procedural step to which it applies

Note:

Used to indicate an operating procedure of such importance that it must be emphasized.

CAUTION:

Used to identify hazards to equipment.

WARNING:

Used to identify hazards to personnel.

A. SCOPE

This master procedure describes the steps necessary to prepare the SMD for transport to the SLC-2W launch site following the completion of P1001B, *Prepare Main Tank for Launch*. These steps include:

Perform P1027, *External Guard Tank Fill- Main Tank Subatmospheric (B1610)* as needed (nominally every four days)

Closeout of the Main Tank:

Perform procedure P1005, *Disconnect Main Tank Vent Line to Gas Module – Main Tank Subatmospheric*

Close RAV-3

Perform additional preparations for FEE closure

Disconnect and secure cabling associated with top plate and main tank bayonet heaters

Open V12

Verify shorting plug installation

Close RAV-6B (commanded by the spacecraft)

Steps to be performed to allow SV rotation for Solar Array installation

If relevant, perform P1016, *Stop Pumping SMD / Disconnect Vacuum Module, and install cap on port*

Perform P1009, *Disconnect Guard Tank Vent Line from Gas Module*

Complete the performance of P1017, *Repump Well with UTS*, to terminate pumping and close out the Well

Steps To Be Performed Prior to Enclosure for Transport to MST

As needed, perform P1017, *Repump Well with UTS*

Perform P1010, *Disconnect Electrical GSE from SMD*

Remove emergency vent lines from burst disks

Note that this procedure is classified as non-hazardous. That classification does not necessarily apply, however, to other procedures that are called by this procedure.

See Figure 1 for the SMD plumbing configuration following the completion of this procedure.

B. SAFETY**B.1. Potential Hazards**

Personal injury and hardware damage can result during normal positioning, assembly and disassembly of hardware.

Liquid helium used in the SMD represents a hazardous material for the personnel involved in the operations. Cryogenic burns can be caused by contact with the

cold liquid or gas, high pressures can result if boiling liquid or cold gas is confined without a vent path, and asphyxiation can result if the vent gas is allowed to accumulate.

During the performance of this procedure the main tank is at subatmospheric pressure. If the main tank fill or vent line is opened to atmosphere, air will be ingested into a cryogenic region where it will freeze with a high probability of blocking of the line. This could prevent proper venting of the main tank on orbit, consequent over temperature and over pressurization, and ultimately the rupturing of one of the main tank burst disks.

The SMD Safety Compliance Assessment, document GPB-100153C discusses the safety design, operating requirements and the hazard analysis of the SMD.

B.2. Mitigation of Hazards

B.2.1. Lifting hazards

There are no lifting operations in this procedure

B.2.2. Cryogenic Hazards

Mitigation of over pressurization hazard is primarily through the use of burst disks or relief valves. A rupture of the main tank burst disk(s) will be obvious due to the plume of cold gas. Emergency vent lines are installed over the burst disks on the SMD vacuum shell to eliminate the possibility of direct plume impingement on personnel. Orderly evacuation shall be performed in the event one or more of these burst disks rupture. An oxygen deficiency monitor (provided by GP-B) that alarms when the oxygen level is reduced to 19.5% will be utilized as an added precaution. Temperature and pressure alarms, provided by the DAS, warn of potential over-pressure conditions.

Only authorized and trained personnel are allowed in VAFB facilities without escort. All personnel working on platforms at a height 30 inches or more off the floor are required to have an approved air tank (emergency breathing apparatus) within easy reach. Note that tank need not be kept available when working from a ladder. In the unlikely event of a large LHe spill all employees have been instructed to evacuate the room and contact NASA and VAFB safety. The following additional requirements apply to all personnel involved directly in cryogenic operations: Insulated gloves when handling equipment that has been cooled to cryogenic temperatures. A protective apron, gloves impervious to liquid cryogenics, impermeable shoes, and full-face shields are to be worn whenever the possibility of splashing or impingement of high velocity cryogenics exists.

B.2.3. Other Hazards

When appropriate, tools or other items used with the potential to damage the SV shall be tethered.

B.3. Mishap Notification

B.3.1. Injury

In case of any injury obtain medical treatment as follows
VAFB Call 911

B.3.2. Hardware Mishap

In case of an accident, incident, or mishap, notification is to proceed per the procedures outlined in Lockheed Martin Engineering Memorandum EM SYS229 and Stanford University GP-B P0879. Additionally, VAFB NASA Safety and 30th Spacewing Safety will be notified as required.

B.3.3. Contingency Response

Responses to contingencies (e.g., power failure, burst disk failure) are listed in Appendix 3.

C. **QUALITY ASSURANCE**

C.1. **QA Notification**

The NASA program and NASA safety representatives and SU QA shall be notified 24 hours prior to the start of this procedure. Upon completion of this procedure, the QE Manager will certify his/her concurrence that the effort was performed and accomplished in accordance with the prescribed instructions by signing and dating in the designated place(s) in this document.

C.2. **Red-line Authority**

Authority to red-line (make minor changes during execution) this procedure is given solely to the TD or his designate and shall be approved by the QA Representative. Additionally, approval by the Payload Technical Manager shall be required, if in the judgment of the TD or QA Representative, mission functionality may be affected.

C.3. **Discrepancies**

A Quality Assurance Representative designated by D. Ross shall review any discrepancy noted during this procedure, and approve its disposition. Discrepancies will be recorded in a D-log or a DR per Quality Plan P0108. Any time a procedure calls for verification of a specific configuration and that configuration is not the current configuration, it represents a discrepancy of one of three types. These types are to be dealt with as described below.

If the discrepancy has minimal effect on procedure functionality (such as the state of a valve that is irrelevant to performance of the procedure) it shall be documented in the procedure, together with the resolution. Redlines to procedures are included in this category.

If the discrepancy is minor and affects procedure functionality but not flight hardware fit or function, it shall be recorded in the D-log. Resolution shall be in consultation with the TD and approved by the QA representative.

All critical and major discrepancies, those that effect flight hardware fit or functions, shall be documented in a D-log and also in a Discrepancy Report, per P0108.

D. TEST PERSONNEL**D.1. Personnel Responsibilities**

The performance of this procedure requires a minimum complement of personnel as determined by the Test Director. However, procedures called by this procedure may have additional requirements. The person performing the operations (Test Director or Test Engineer) is to sign the "Completed by" sign-off. Any other qualified person or QA person who can attest to the successful performance of this procedure may sign the "Witnessed by" sign-off. **The Test Director will perform pre-test and Post-Test briefings in accordance with P0875 "GP-B Maintenance and Testing at all Facilities". Checklists will be used as directed by P0875.**

D.2. Personnel Qualifications

The Test Director must have a detailed understanding of all procedures and facility operations and experience in all of the SMD operations. Test Engineers must have SMD Cryogenic operations experience and an understanding of the operations and procedures used for the cryogenic servicing/maintenance of the Dewar.

D.3. Required Personnel

List below those personnel involved with the procedure

The following personnel are essential to the accomplishment of this procedure:

| FUNCTIONAL TITLE | NUMBER | AFFILIATION |
|-----------------------------|--------|----------------|
| Test Director/Test Engineer | 1 | Stanford |
| GP-B Quality Assurance | 1 | Stanford |
| NASA Safety Rep | 1 | SFAO or ANALEX |

E. REQUIREMENTS**E.1. Electrostatic Discharge Requirements**

Any person who comes in contact with the SV must use a grounding wrist strap that has been tested that day. Appropriate attachment points are positioned around the SV.

E.2. Lifting Operation Requirements

There are no lifting operations in this procedure

E.3. Hardware/Software Requirements**E.3.1. Commercial Test Equipment**

No commercial test equipment is required for this operation.

E.3.2. Ground Support Equipment

The Ground Support Equipment includes the Gas Module (GM), the Pump Module (PM), the Electrical Module (EM), the Vacuum Module (VM), and the Utility Turbopump System (UTS). The Gas Module provides the capability to configure vent paths, read pressures and flow rates, and pump and backfill vent lines. The Pump Module provides

greater pumping capacity than the Gas Module, together with additional flow metering capabilities. The vent output of the Gas Module flows through the Pump Module. The Electrical Module contains the instruments listed in Table 1 (see the Electrical Module Manual for details) and provides remote control of valves in the Gas Module, Pump Module, and SMD. The Vacuum Module contains a turbo pump, backed by a vane pump and provides the capability to pump out the SMD vacuum shell. The UTS is a smaller version of the Vacuum Module.

This procedure calls for use of hardware located in the Gas Module (Figure 2), the Electrical Module (Table 1), and the UTS (Figure 3).

E.3.3. Computers and Software

The Data Acquisition System (DAS) and data acquisition software are required for this procedure. The DAS reads and displays pressures, temperatures, and flow rates and monitors critical parameters. No additional computers or software are required.

E.3.4. Spacecraft Support

With connector J802 connected to flight electronics, operation of RAV-2 and RAV-6B must be commanded through the spacecraft instead of the RAV controller in the Electrical Module. Spacecraft telemetry and EGSE support will also be needed.

E.3.5. Additional Test Equipment

| <i>Description</i> | <i>Manufacturer</i> | <i>Model</i> |
|----------------------------------|-------------------------|--------------|
| O ₂ Monitor and Alarm | Alpha-Omega Instruments | 1000 |

E.3.6. Additional Hardware

No additional hardware is required

E.3.7. Protective Clothing

None required.

E.3.8. Tools

No tools are required for this operation.

E.3.9. Expendables

| <i>Description</i> | <i>Quantity</i> | <i>Mfr./Part No.</i> |
|--------------------|-----------------|----------------------|
| Liquid Helium | ≥ 500 liters. | N/A |

E.4. **Instrument Pretest Requirements**

The GSE instruments required to perform this procedure are listed in Table 1, together with their serial numbers, where available. Instruments that are required to have current calibrations are indicated in the Cal-Required column. Instruments that do not require calibration are those not used to verify performance requirements and are not connected to flight instrumentation. The status column is to be filled in with the due date of the instrument calibration sticker and verified to be in calibration by QE or QE designee. Serial numbers are to be updated as appropriate.

Table 1. Required Instrumentation and Calibration Status

| <i>No.</i> | <i>Location</i> | <i>Description</i> | <i>User Name</i> | <i>Serial No.</i> | <i>Cal Required</i> | <i>Status Cal due date</i> |
|------------|-----------------|-------------------------|------------------|-------------------|---------------------|----------------------------|
| 1 | DAS | Power Supply, H-P 6627A | - A1, A2, A3, A4 | 3452A01975 | Yes | |
| 2 | DAS | Power Supply, H-P 6627A | B1, B2, B3, B4- | 3452A01956 | Yes | |

| No. | Location | Description | User Name | Serial No. | Cal Required | Status Cal due date |
|------------|-----------------|---|---------------------|-------------------|---------------------|--------------------------------|
| 3 | DAS | Data Acquisition/Control Unit H-P 3497A | - | 2936A245539 | No | - |
| 4 | DAS | Digital Multimeter H-P 3458A | - | 2823A15047 | Yes | |
| 5 | EM | Vacuum Gauge Controller Granville-Phillips Model 316 | EG-1a, -1b | 2827 | No | - |
| 6 | EM | Vacuum Gauge Controller Granville-Phillips Model 316 | AG-2a, -2b | 2826 | No | - |
| 7 | EM | Vacuum Gauge Controller Granville-Phillips Model 316 | EG-3 | 2828 | No | - |
| 8 | EM | MKS PDR-C-2C | EG-2, FCG | 92022108A | No | - |
| 9 | EM | Flow meter – Matheson 8170 | EFM-1 | 96186 | No | - |
| 10 | EM | Flow meter totalizer Matheson 8124 | EFM-1 | 96174 | No | - |
| 11 | EM | Liquid Helium Level Controller American Magnetics, Inc. 136 | LLS Main Tank | 96-409-11 | No | - |
| 12 | EM | Liquid Helium Level Controller American Magnetics, Inc. 136 | LLS Guard Tank | 96-409-10 | No | - |
| 13 | EM | Liquid Helium Level Controller American Magnetics, Inc. 136 | LLS Well | 96-409-9 | No | - |
| 14 | EM | Liquid Helium Level Controller American Magnetics, Inc. 136 | LLS Axial Lock | 96-409-12 | No | - |
| 15 | EM | Pressure Controller – MKS 152F-92 | EV-7a, -7b | 96203410A | No | - |
| 16 | EM | Power Supply HP 6038A | H08D Tank Heater | 96023407A | Yes | |
| 17 | EM | Power Supply HP 6038A | H09D Tank Heater | 3511A-13332 | Yes | |
| 18 | EM | Power Supply HP 6038A | RAV Power Supply | 3329A-12486 | Yes | |
| 19 | EM | Vac Ion Pump power supply Varian 929-0910, Minivac | SIP | 5004N | No | - |
| 20 | EM | Flow meter totalizer Veeder-Root | PFM-1 | 576013-716 | No | - |
| 21 | GM | Pressure Gauge, Heise | AG-1 | CC-122077 | No | - |
| 22 | GM | Pressure Gauge, Marshall Town | AG-3 | N/A | No | - |
| 23 | GM | Main Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller | EH-1 | C-19950 | No | - |
| 24 | GM | Guard Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller | EH-2 | C-09920 | No | - |
| 25 | VM | Vacuum Gauge readout, Granville-Phillips 316 | VG-3 VG-4 | 2878 | No | - |
| 26 | VM | Vacuum Gauge readout, Granville-Phillips 360 | VG-1, VG-2 VG-5 | 96021521 | No | - |

E.5. Configuration Requirements

E.5.1. Space Vehicle

The SV must be mounted vertical (+Z up) in the Assembly Stand with the FEE skins removed to allow to the vent boss region. The FEE skins and the solar panels may be installed for the latter part of this procedure.

E.5.2. Main Tank

The Main Tank liquid must be subatmospheric (1.65 K) with the liquid level $\geq 95\%$ as obtained by the completion of P1001, *Prepare Main Tank for Launch*. The Main Tank is being pumped by AP-1 as specified in P1001, Sec. G.15. The actuator control valve for EV-9 (located on the Gas Module, this valve switches the state that EV-9 defaults to, should a power failure occur) should be verified in the "Subatm He" position, at the beginning of this procedure, ensuring that EV-9 closes in the event of power failure.

E.5.3. Guard Tank

The Guard Tank is filled with NBP liquid He and must be maintained above a minimum level of 20%. The Guard Tank pressure must not be allowed to drop below atmospheric.

E.5.4. Well

The Well must be evacuated with the UTS connected to the Well pumpout port per P1001, *Prepare the Main Tank for Launch*.

E.5.5. SMD Vacuum Shell

The Vacuum Shell pressure must be less than 5×10^{-5} torr. Procedure P1015, *Connect Vacuum Module to SMD*, contains the steps for connecting to and pumping on the SMD vacuum shell.

E.5.6. Alarm System

1. The DAS alarm system must be enabled and contain the following alarm set-points:
 - a. Top of lead bag temperature (CN 175) set at $T \leq 6.0$ K.
 - b. Top of lead bag temperature set (CN 178) at $T \leq 6.0$ K.
 - c. Relative Guard Tank Pressure (CN 46) set at $\Delta P \geq 30$ torr.
2. The DAS watchdog timer and alarm are enabled.

E.5.7. GSE and Non-flight Hardware

1. The ion-pump magnet is installed and ion pump is cabled to its readout.
2. GSE cabling must be connected between the SMD and the Electrical Module (P/N 5833812) and between the SMD and the Data Acquisition System (P/N 5833811).
3. The Main Tank vent line must be connected to the Gas Module with a vacuum insulated line (P/N 5833806).

4. The Guard Tank vent line must be connected to the Gas Module with a vacuum insulated line (P/N 5833813).
5. The Fill Cap Assembly must be installed at SV-13.
6. The heaters on the SMD top plate, SV-9, and Main Tank vent bayonet are installed and connected to the External Temperature Control Unit.
7. The Pump Module is connected to the Gas module at EV-21.
8. The Utility Turbopump System is connected to the Well, but may be in a valved-off state per P1001.
9. Facility vent lines must be connected per P1000

E.6. Optional Non-flight Configurations

N/A

E.7. Verification/Success Criteria

N/A

E.8. Payload Constraints and Restrictions

N/A

F. REFERENCE DOCUMENTS

F.1. Drawings

| <i>Drawing No.</i> | <i>Title</i> |
|---------------------------|-------------------------------------|
| LMMS-5833394 | <i>Instrumentation Installation</i> |

F.2. Supporting documentation

| <i>Document No.</i> | <i>Title</i> |
|--|--|
| LMMS-5835031 | <i>GP-B Magnetic Control Plan</i> |
| GPB-100153C | <i>SMD Safety Compliance Assessment</i> |
| LMSC-P088357 | <i>Science Mission Dewar Critical Design Review</i> |
| SU/GP-B P0108 | <i>Quality Plan</i> |
| LMMS GPB-100333 | <i>Science Mission Dewar Failure Effects and Causes Analysis</i> |
| SU/GP-B P059 | <i>GP-B Contamination Control Plan</i> |
| LM EM SYS229 | <i>Accident/Incident/Mishap Notification Process</i> |
| EWR 127-1, 31 March 1995, Eastern and Western Range Safety Requirements | <i>Hazardous and Safety Critical Procedures</i> |
| KHB 1710, rev D | <i>Kennedy Space Center Safety Practices Handbook</i> |
| SU/GP-B P1001B | <i>Prepare Main Tank for Launch (as-run copy)</i> |

F.3. Additional Procedures

| <i>Document No.</i> | <i>Title</i> |
|----------------------------|--|
| SU/GP-B P1005A | <i>Disconnect Main Tank Vent Line to Gas Module – Main Tank Subatmospheric</i> |

| | |
|---------------|---|
| SU/GP-B P1017 | <i>Repump Well with UTS</i> |
| SU/GP-B P1027 | <i>External Guard Tank Fill- Main Tank Subatmospheric (B1610)</i> |
| SU/GP-B P1009 | <i>Disconnect Guard Tank Vent Line from Gas Module</i> |
| SU/GP-B P1010 | <i>Disconnect Electrical GSE from SMD</i> |
| SU/GP-B P1016 | <i>Stop Pumping SMD / Disconnect Vacuum Module</i> |

Operation Number: _____

Date Initiated: _____

Time Initiated: _____

G. OPERATIONS

G.1. Pre-Operations Verifications

- Verify SU QA notified.
Record: Individual notified _____,
Date/time _____/_____.
- Verify NASA program representative notified.
Record: Individual notified _____,
Date/time _____/_____.
- Verify NASA Safety representative has been notified and has given concurrence to proceed.
Record: Individual notified _____,
Date/time _____/_____.
- Verify that the persons performing this procedure, the test director, and safety engineer are identified in Sec. D.3.
- Verify performance of pre-operations checklist (Appendix 1).

Section complete _____ QA.

G.2. Verify Preliminary SMD and GSE Preparations Complete

- G.2.1. Verify that ~500 liters or more of liquid He is available.
- G.2.2. Verify successful completion of P1001B, *Prepare Main Tank for Launch*.
Record Op. No.: _____
Comment: This verifies that the Main Tank has been filled to 95% and cooled to 1.65 K or less. It also verifies that the vacuum shell and Well have been evacuated.
- G.2.3. Verify operation of the GP-B portable oxygen monitor.

Section complete _____ QA.

G.3. Verify Configuration Requirements

- G.3.1. Verify SV configuration: in Assembly Stand with FEE skins and solar panels not yet installed.

- G.3.2. Main Tank: Verify the following by reference to P1001B, *Prepare Main Tank for Launch*:
1. Main Tank 95 ±1% full (94.3 ±1% indicated);
 2. Main Tank bath at 1.65 K or less;
 3. Main Tank pumped by AP-1;
 4. EV-9 actuator control valve for EV-9 on “Subatm. He”.
- G.3.3. Verify the Guard Tank is filled with NBP liquid He and liquid level is above a minimum level of 20%:
Record GT liquid level: _____ %

- G.3.4. Vacuum status: Verify the following by reference to P1001B, *Prepare Main Tank for Launch*:
1. Well is evacuated, and the UTS running and connected to the Well pumpout port; Record pumping status:

 2. Verify that the vacuum shell pressure is less than 5×10^{-5} torr (G.16.15 of P1001B).

G.3.5. Ensure GSE cabling connected between SMD and Electrical Module and between SMD and Data Acquisition System.

G.3.6. Verify valve / pump status:

| Open / On: | Closed / Off: |
|--------------------------------|--|
| EV-7a/-7b, EV-10, EV-17, EV-13 | All other EVs |
| AP-1, AV-6, AV-8 (opt.) | All other AVs |
| SV-9, GTV-V | FCV, SV-12, SV-13, all other GTV and GTVC valves |
| TP-1, TP-2, TV-1 (opt.), TV-2 | All other TV valves |
| VW-1, VW-2, VW-3 (opt.) | – |
| RAV-3, RAV-6B | All other RAVs |

G.3.7. Ensure DAS alarm system enabled and record set points.

1. **Top of lead bag temperature** – ensure CN [175] on DAS alarm list and set to alarm at $T \leq 6.0$ K.
Record set point. _____ K
2. **Top of lead bag temperature** – ensure CN [178] on DAS alarm list and set to alarm at $T \leq 6.0$ K.
Record set point. _____ K
3. **Relative Guard Tank Pressure** – ensure CN [46] on DAS alarm list and set to alarm at $\Delta P \geq 30$ torr.
Record set point. _____ torr

G.3.8. Ensure DAS watchdog timer and alarm enabled.

G.3.9. Verify ion-pump magnet and cable are installed.

- G.3.10. Verify Main Tank vent line connected to Gas Module.
- G.3.11. Verify Guard Tank vent line connected to Gas Module.
- G.3.12. Verify Fill Cap Assembly installed at SV-13

Section complete _____ QA.

G.4. Guard Tank Fill Operations

- G.4.1. Perform P1027, *External Guard Tank Fill- Main Tank Subatmospheric (B1610)* or P1052, *External Guard Tank Fill – Main Tank Subatmospheric and No Vent Lines Connected* (as appropriate) when needed (nominally every four days). Record date and op. no. for each occasion:

| Date | Op. Order No. |
|------|---------------|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

G.5. Closeout of the Main Tank

Comment: This section must be performed before FEE closeout.

- G.5.1. Perform procedure P1005, *Disconnect Main Tank Vent Line to Gas Module – Main Tank Subatmospheric*.
Record: Date _____ Op. No. _____.
Comment: P1005 closes SV-9, verifies closure, removes the vent line, installs flight cap, and evacuates and leak checks the cap.
- G.5.2. Verify that the main tank vent cap is oriented per the mass properties tests (valve stem approximately in the X-Y plane).

Note:
Closure of RAV-3 shall be observed by the Payload Test Director.

- G.5.3. Close RAV-3 as follows:
 1. Verify that P803/J803 are connected.
 2. Ensure all RAV controller selection switches in OFF position.
 3. Turn on RAV power supply and adjust current limit to 1.85 amps.
 4. Adjust power supply to 28 VDC.
 5. Power up controller #3.

6. Position selection switch for controller #3 to RAV-3.
7. Record initial status lights (4) on: Open: θ θ Closed: θ θ
8. Activate controller #3 to close RAV-3 and record:
 - a. Run time: _____ seconds.
 - b. Current draw: _____ amps.
 - c. Time of day: _____.
9. Record final status lights (4) on: θ θ Closed: θ θ
10. Verify that at least one of the closed status lights is illuminated.
11. Record operation in RAV log book.

RAV-3 closure complete _____ QA.

_____ PTD.

G.6. Additional Preparations for FEE Closure

- G.6.1. Disconnect all cabling for the Main Tank vent and top plate heaters and secure with flight cable ties. Do not disturb the Guard Tank bayonet heater cabling.

Note:
Opening of V12 (SV-12) shall be observed or verified by the Payload Test Director.

- G.6.2. Configure the thruster vent for FEE closeout (see Fig. 1) as follows:
 1. Slowly open SV-12. (Comment: There is an atmosphere of helium in the volume between RAV4A/B and SV-12, whereas the main tank is subatmospheric.)
 - a. LM to epoxy stake SV-12 open per drawing 8A00288.
Record Op. No. _____.

SV-12 open and secured _____ QA.

_____ PTD.

- G.6.3. Before installation of the solar panels, verify that the following dewar-related items have been performed:
 1. Shorting plug is installed at P803A (spacecraft operation).
 2. Shorting plug is installed at P6 (spacecraft operation).
 3. Verify umbilical P800 and P804 are connected to the bottom of the FEE and are staked.

G.7. Closure of RAV-6B

Comment: This section may be performed at any convenient time as is needed to coordinate with POD G.

G.7.1. Inform spacecraft operations personnel of impending RAV-6B operation.

G.7.2. Restart pumping on the Well as follows:

1. Verify the UTS turbopump is running and connected to the Well pumpout port.
2. Open / verify open TV-1.
3. Wait until TG-1 reads below 10^{-5} torr.
4. Open VW-3/4 to resume pumping on the Well.

G.7.3. Pump on the Well for a minimum of two hours before proceeding

G.7.4. Close RAV-6B as follows:

1. Verify that the Spacecraft is powered up, arming plug P222 is installed, and control personnel are prepared to command RAV-6B when requested.
2. Request spacecraft operations personnel to close RAV-6B and record date/time upon telemetry confirmation of valve closure
_____/_____.
3. Verify removal of arming plug P222.

G.8. Steps To Be Performed to Allow SV Rotation for Solar Array Installation

G.8.1. If the Vacuum Module is connected to the vacuum shell pumpout port, PO, perform P1016, *Stop Pumping SMD / Disconnect Vacuum Module*, to discontinue pumping and completely disconnect the Vacuum Module.

G.8.2. Install the cap on the pumpout port PO, and request LM safety wire per MS33540. (Comment: It is not expected that the SMD vacuum shell will need further servicing before launch.)

_____ QA.

G.8.3. Perform P1009, *Disconnect Guard Tank Vent Line from Gas Module*, and record Op. No.: _____

G.8.4. Continue to pump on the Well for at least four hours after completion of the last Guard Tank fill procedure prior to SV rotation.

G.8.5. Complete the performance of P1017, *Repump Well with UTS*, to terminate pumping and close out the Well.

G.9. Steps To Be Performed Prior to Enclosure for Transport to MST

G.9.1. As needed, perform P1017, *Repump Well with UTS*, with pumping duration as long as practicable. Record date and op. order number for

each occasion:

| Date | Op. Order No. |
|------|---------------|
| | |
| | |
| | |
| | |
| | |
| | |
| | |

G.9.2. When needed to enclose the SV for transport, remove the emergency facility vent lines from the four burst disks, BD5A/B and BD7A/B leaving the manifolds in place. Install plastic protective covers.

Section complete _____ QA.

H. PROCEDURE COMPLETION

Completed by: _____

Witnessed by: _____

Date: _____

Time: _____

Quality Manager _____ **Date** _____

Payload Test Director _____ **Date** _____




Figure 1 Schematic representation of SMD after completion of this procedure.




Figure 2. Schematic of Gas Module Plumbing.




Figure 3. Schematic diagram of Utility Turbopump System (UTS)

I. APPENDIX 1 – PRE-PROCEDURE CHECKLIST

| DATE | CHECKLIST ITEM | COMPLETED | REMARKS |
|------|--|-----------|---------|
| | 1. Verify the test procedure being used is the latest revision. | | |
| | 2. Verify all critical items in the test are identified and discussed with the test team. | | |
| | 3. Verify all required materials and tools are available in the test area. | | |
| | 4. Verify all hazardous materials involved in the test are identified to the test team. | | |
| | 5. Verify all hazardous steps to be performed are identified to the test team. | | |
| | 6. Verify each team member knows their individual responsibilities. | | |
| | 7. CONFIRM THAT EACH TEST TEAM MEMBER CLEARLY UNDERSTANDS THAT HE/SHE HAS THE AUTHORITY TO STOP THE TEST IF AN ITEM IN THE PROCEDURE IS NOT CLEAR. | | |
| | 8. Confirm that each test team member clearly understands that he/she must stop the test if there is any anomaly or suspected anomaly. | | |
| | 9. NOTIFY MANAGEMENT OF ALL DISCREPANCY REPORTS OR D-LOG ITEMS IDENTIFIED DURING PROCEDURE PERFORMANCE. IN THE EVENT AN INCIDENT OR MAJOR DISCREPANCY OCCURS DURING PROCEDURE PERFORMANCE MANAGEMENT WILL BE NOTIFIED IMMEDIATELY. | | |
| | 10. Confirm that each test team member understands that there will be a post-test team meeting. | | |
| | Team Lead Signature: _____ | | |

J. APPENDIX 2 – POST-PROCEDURE CHECKLIST

| DATE | CHECKLIST ITEM | COMPLETED | REMARKS |
|------|--|-----------|---------|
| | | | |
| | 1. Verify all steps in the procedure were successfully completed. | | |
| | | | |
| | 2. Verify all anomalies discovered during testing are properly documented. | | |
| | | | |
| | 3. Ensure management has been notified of all major or minor discrepancies. | | |
| | | | |
| | 4. Ensure that all steps that were not required to be performed are properly identified. | | |
| | | | |
| | 5. If applicable sign-off test completion. | | |
| | | | |
| | 6. Verify all RAV valve operations have been entered in log book | | |
| | | | |
| | 7. Verify the as-run copy of procedure has been filed in the appropriate binder | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | Team Lead Signature: | | |

K. **APPENDIX 3– CONTINGENCY RESPONSES**

| | Condition | Circumstance | Response |
|---|----------------------------|---|--|
| 1 | Power Failure | Before closeout of the main tank, section G.4.1 | <ol style="list-style-type: none"> 1) Verify EV-9 and all other EVs and AVs are closed 2) Close / verify closed VW-3 3) Verify that all TVs are closed 4) Upon restoration of <u>utility</u> power, verify AP-1 is now running 5) Open AV-8 and verify that the pressure read by AG-2b is less than 0.1 torr 6) Open in sequence AV-6, EV-10, EV-17 to re-establish pumping on the MT 7) Reopen EV-13 8) Restart UTS per P1017 9) Continue with procedure |
| | | After closeout of the MT per P1005 | <ol style="list-style-type: none"> 1) Verify that all TVs are closed 2) Close / verify closed VW-3 3) Upon restoration of utility power, restart UTS per P1017 4) Continue with procedure |
| 2 | Burst disk rupture (MT/GT) | Any time | Evacuate room |
| 3 | Oxygen depletion alarm | Any time | Evacuate room |