

# GRAVITY PROBE B PROCEDURE FOR SCIENCE MISSION DEWAR

## Internal Guard Tank Fill – Vent Lines Disconnected

To be performed at Vandenberg Air Force Base building 1610

**THIS DOCUMENT CONTAINS NON HAZARDOUS OPERATIONS**

P1026

October 1, 2002

Written by

Checked by

\_\_\_\_\_ Date \_\_\_\_\_

\_\_\_\_\_ Date \_\_\_\_\_

Ned Calder  
Cryogenic Test

Dave Murray  
Cryogenic Test

Approvals:

\_\_\_\_\_ Date \_\_\_\_\_

\_\_\_\_\_ Date \_\_\_\_\_

Dorrene Ross  
Quality Assurance

Harv Moskowitz  
LMMS Safety

\_\_\_\_\_ Date \_\_\_\_\_

\_\_\_\_\_ Date \_\_\_\_\_

Rob Brumley  
Payload Technical Manager

Mike Taber  
Payload Test Director

\_\_\_\_\_ Date \_\_\_\_\_

NASA/KSC Safety

-

**REVISION RECORD**

REV	ECO	PAGES	DATE

**Table of Contents**

A. SCOPE	1
B. SAFETY	2
B.1. Potential Hazards	2
B.2. Mitigation of Hazards	2
B.3. Mishap Notification	3
C. QUALITY ASSURANCE	3
C.1. QA Notification	3
C.2. Red-line Authority	3
C.3. Discrepancies	4
D. TEST PERSONNEL	4
D.1. Personnel Responsibilities	4
D.2. Personnel Qualifications	4
D.3. Required Personnel	4
E. REQUIREMENTS	4
E.1. Electrostatic Discharge Requirements	5
E.2. Lifting Operation Requirements	5
E.3. Hardware/Software Requirements	5
E.4. Instrument Pretest Requirements	6
E.5. Configuration Requirements	7
E.6. Optional Non-flight Configurations	7
F. REFERENCE DOCUMENTS	9
F.1. Drawings	9
F.2. Supporting documentation	9
F.3. Additional Procedures	9
G. OPERATIONS	10
G.1. Pre Operations Verifications	10
G.2. Verify Purity of All Sources of Helium Supply	10
G.3. Verify Configuration Requirements	10
G.4. Verify SMD in Standard Configuration	12
G.5. Establish Vent Line Configuration and Record Initial Conditions	12
G.6. Check Initial pressure in Fill Line	12
G.7. Set up Data Acquisition	13
G.8. Raise Pressure in Fill Line by opening RAV-1 and close SV-9	13
G.9. Prepare to Transfer	14
G.10. Initiate Transfer	14
G.11. Terminate Transfer to Guard Tank	15
G.12. Condition Dewar Fill Line and Fill Cap Assembly.	16
G.13. Configure the DAS and Liquid Level Sensors	17
G.14. Verify Final Configuration	19
H. PROCEDURE SIGN OFF	19
I. APPENDIX 1 PRE OPERATIONS CHECKLIST	22
J. APPENDIX 2 POST OPERATIONS CHECKLIST	25
K. APPENDIX 3 CONTINGENCY RESPONSES	26

**List of Abbreviations and Acronyms**

AG-x	Gauge x of Gas Module auxiliary section	MT	Main Tank
AMI	American Magnetics Inc.	MTVC	Main Tank Vent Cap
ATC	Advanced Technology Center	MTVC-G	Main Tank Vent Cap pressure gauge
Aux	Auxiliary	MTVC-RV	Main Tank Vent Cap relief valve
AV-x	Valve x of Gas Module auxiliary section	MTVC-V	Main Tank Vent Cap valve
Bot	Bottom	NBP	Normal boiling point
CN [xx]	Data acquisition channel number	ONR	Office of Naval Research
DAS	Data Acquisition System	PFCG	Fill Cap assembly pressure Gauge
EFM	Exhaust gas Flow Meter	PFM	Pump equipment Flow Meter
EG-x	Gauge x of Gas Module exhaust section	PG-x	Gauge x of Pump equipment
EM	Electrical Module	PM	Pump Module
ERV-x	Relief valve of Gas Module exhaust section	psi	pounds per square inch
EV-x	Valve number x of Gas Module exhaust section	psig	pounds per square inch gauge
FCV	Fill Cap Valve	PTD	Payload Test Director
FIST	Full Integrated System Test	PV-x	Valve x of the Pump equipment
GHe	Gaseous Helium	QA	Quality Assurance
GM	Gas Module	RAV-x	Remote Actuated Valve-x
GP-B	Gravity Probe-B	RGA	Residual Gas Analyzer
GSE	Ground Support Equipment	SMD	Science Mission Dewar
GT	Guard Tank	STV	SMD Thruster vent Valve
GTVC	Guard Tank Vent Cap	SU	Stanford University
GTVC-G	Guard Tank Vent Cap pressure gauge	SV-x	SMD Valve number x
GTVC-RV	Guard Tank Vent Cap relief valve	TG-x	Gauge x of Utility Turbo System
GTVC-V	Guard Tank Vent Cap valve	TV-x	Valve x of Utility Turbo System
GTV-G	Guard Tank vent pressure gauge	UTS	Utility Turbo System
GTV-RV	Guard Tank vent relief valve	Vac	Vacuum
GTV-V	Guard Tank vent valve	VCP-x	Vent cap pressure gauge
HX-x	Vent line heat exchanger in Gas Module	VCRV-x	Vent cap relief valve
KFxx	Quick connect o-ring vacuum flange (xx mm diameter)	VCV-x	Vent cap valve
LHe	Liquid Helium	VDC	Volts Direct Current
LHSD	Liquid Helium Supply Dewar	VF-x	Liquid helium Fill line valve
Liq	Liquid	VG-x	Gauge x of Vacuum Module
LL	Liquid level	VM	Vacuum Module
LLS	Liquid level sensor	VV-x	Valve x of Vacuum Module
LMMS	Lockheed Martin Missiles and Space	VW-x	Valve x of Dewar Adapter
LMSC	Lockheed Missiles and Space Co.		

-

**LIST OF SPECIFIC HEADING DEFINITIONS**

Each type of alert message will precede the procedural step to which it applies

1. NOTE: Used to indicate an operating procedure of such importance that it must be emphasized
2. CAUTION: Used to identify hazards to equipment
3. WARNING: Used to identify hazards to personnel

**A. SCOPE**

This procedure describes the steps necessary to transfer normal boiling point liquid helium from the Main Tank to the Guard Tank of the Science Mission Dewar, while the Main and Guard Tanks are both disconnected from the Gas Module. The steps include;

Raise Main Tank Pressure- Close SV-9 and use Main Tank heaters

Raise internal fill line pressure to Main Tank pressure – open RAV-1.

Decrease Guard Tank pressure – open Guard Tank vent valve on Vent Cap.

Initiate transfer – open RAV-2.

Terminate transfer – close RAV-1 and RAV-2.

The Main Tank liquid must be at normal boiling point. All RAV-2 operations are to be performed by the LM personnel and the ECU

This is a non-hazardous operation that transfers liquid helium from one internal tank into another internal tank.

**B. SAFETY****B.1. Potential Hazards**

Personal injury and hardware damage can result during normal positioning, assembly and disassembly of hardware.

Liquid helium used in the SMD represents a hazardous material for the personnel involved in the operations. Cryogenic burns can be caused by contact with the cold liquid or gas, high pressures can result if boiling liquid or cold gas is confined without a vent path, and asphyxiation can result if the vent gas is allowed to accumulate.

The SMD Safety Compliance Assessment, document GPB-100153C and the Missile System Prelaunch Safety Package discuss the safety design, operating requirements and the hazard analysis of the SMD.

**B.2. Mitigation of Hazards****B.2.1. Lifting hazards**

There are no lifting operations in this procedure

**B.2.2. Cryogenic Hazards**

In VAFB building 1610, the GP-B cryogenic team provides an oxygen deficiency monitor that alarms when the oxygen level is reduced to 19.5%. Additional temperature and pressure alarms, provided by the DAS, warn of potential over-pressure conditions. Emergency vent lines are installed over the four burst disks to direct any flow to an outside area.

Only authorized and trained personnel are allowed in VAFB facilities without escort. All personnel working on platforms at a height 30 inches or more off the floor are required to have an approved air tank

(emergency breathing apparatus) within easy reach. Note that the tank need not be kept available when working from ladder. In the unlikely event of a large LHe spill all employees have been instructed to evacuate the room and contact NASA and VAFB safety.

The following additional requirements apply to all personnel involved directly in cryogenic operations. Gloves that are impervious to liquid helium and liquid nitrogen are to be worn whenever the possibility of splashing or impingement of high-velocity cryogenics exists or when handling equipment that has been cooled to cryogenic temperatures. Protective clothing, non-absorbent shoes and full-face shields/with goggles/glasses are to be worn whenever the possibility of splashing cryogenics exists.

#### B.2.3. Other Hazards

When appropriate, tools or other items used with the potential to damage the space vehicle shall be tethered..

### B.3. Mishap Notification

#### B.3.1. Injury

In case of any injury or illness requiring emergency medical treatment **DIAL 911.**

#### B.3.2. Hardware Mishap

In case of an accident, incident, or mishap, notification is to proceed per the procedures outlined in Lockheed Martin Engineering Memorandum EM SYS229 and Stanford University GP-B P0879. Additionally, VAFB NASA Safety and 30<sup>th</sup> Space Wing Safety will be notified as required

#### B.3.3. Contingency Response

Responses to contingencies (e.g., power failure) are listed in Appendix 3.

## C. QUALITY ASSURANCE

### C.1. QA Notification

***The NASA program and the NASA safety representative and SU QA shall be notified 24 hours prior to the start of this procedure.*** Upon completion of this procedure, the QE Manager will certify his/her concurrence that the effort was performed and accomplished in accordance with the prescribed instructions by signing and dating in the designated place(s) in this document.

### C.2. Red-line Authority

Authority to red-line (make minor changes during execution) this procedure is given solely to the TD or his designate and shall be approved by the QA Representative. Additionally, approval by the Payload Technical Manager shall

be required, if in the judgement of the TD or QA Representative, experiment functionality may be affected.

### C.3. Discrepancies

A Quality Assurance Representative designated by D. Ross shall review any discrepancy noted during this procedure, and approve its disposition.

Discrepancies will be recorded in a D-log or a DR per Quality Plan P0108. Any time a procedure calls for verification of a specific configuration and that configuration is not the current configuration, it represents a discrepancy of one of three types. These types are to be dealt with as described below.

1. If the discrepancy has minimal effect on procedure functionality (such as the state of a valve that is irrelevant to performance of the procedure) it shall be documented in the procedure, together with the resolution. Redlines to procedures are included in this category.
2. If the discrepancy is minor and affects procedure functionality but not flight hardware fit or function, it shall be recorded in the D-log. Resolution shall be in consultation with the PTD and approved by the QA representative.
3. All critical and major discrepancies, those that effect flight hardware fit or functions, shall be documented in a D-log and also in a Discrepancy Report, per P0108.

## D. TEST PERSONNEL

### D.1. Personnel Responsibilities

The performance of this procedure requires a minimum complement of personnel as determined by the Test Director. The Test Director is the designated signer for the “witnessed by” sign-off located at the end of each procedure. The person in charge of the operation (Test Director or Test Engineer) is to sign the “completed by” sign-off. The Test Director will perform Pre-Test and Post-Test Briefings in accordance with P0875 “GP-B Maintenance and Testing at all Facilities.” Checklists will be used as directed by P0875

### D.2. Personnel Qualifications

The Test Director must have a detailed understanding of all procedures and facility operations and experience in all of the SMD operations. Test Engineers must have SMD Cryogenic operations experience and an understanding of the operations and procedures used for the cryogenic servicing/maintenance of the Dewar.

### D.3. Required Personnel

The following personnel are essential to the accomplishment of this procedure:

FUNCTIONAL TITLE	NUMBER	AFFILIATION
Test Director/Test Engineer	1	Stanford
GP-B Quality Assurance	1	Stanford



**E. REQUIREMENTS****E.1. Electrostatic Discharge Requirements**

When working on the space vehicle, proper ESD protection is required. All Wrist straps will be checked on an appropriate calibrated checker prior to use.

**E.2. Lifting Operation Requirements**

There are no lifting operations in this procedure

**E.3. Hardware/Software Requirements****E.3.1. Commercial Test Equipment**

No commercial test equipment is required for this operation.

**E.3.2. Ground Support Equipment**

The Ground Support Equipment includes the Gas Module, the Electrical Module. The Gas Module provides the capability to configure vent paths, read pressures and flow rates, and pump and backfill vent lines. The Pump Module provides greater pumping capacity than the Gas Module, together with additional flow metering capabilities. The vent output of the Gas Module flows through the Pump Module. The Electrical Module contains the instruments listed in Table 1, and provides remote control of valves in the Gas Module, Pump Module, and SMD.

This procedure calls for use of hardware located in the Gas and Electrical Modules.

**E.3.3. Computers and Software:**

The Data Acquisition System (DAS) is required for this procedure. The DAS reads and displays pressures, temperatures, and flow rates and monitors critical parameters. No additional computers or software are required.

**E.3.4. Additional Test Equipment****E.3.5. Additional Hardware****E.3.6. Tools**

<i>Description</i>
Torque Wrench, 1-1/4-in socket, 60 +/- 5 in-lb Cal Due Date: _____ S/N _____

**E.3.7. Expendables****WARNING**

**Ethanol is highly flammable and vapor/air mixtures are Explosive.**  
**Exposure hazards include: Inhalation (headache/fatigue),**  
**skin (dryness, eyes (redness/pain/burning))**

<i>Description</i>	<i>Quantity</i>	<i>Mfr./Part No.</i>
Ethanol	AR	N/A
99.999% pure gaseous helium	AR	N/A
Vacuum Grease	AR	Dow Corning High Vacuum or Apiezon N

#### E.4. Instrument Pretest Requirements

The GSE instruments required to perform this procedure are listed in Table 1, together with their serial numbers, where available. Instruments that are required to have current calibrations are indicated in the Cal-Required column. Instruments that do not require calibration are those not used to verify performance requirements and are not connected to flight instrumentation. The status column is to be filled in with the due date of the instrument calibration sticker and verified to be in calibration by QE or QE designee.

**Table 1. Required Instrumentation and Calibration Status**

<i>No.</i>	<i>Location</i>	<i>Description</i>	<i>User Name</i>	<i>Serial No.</i>	<i>Cal Required</i>	<i>Status Cal due date</i>
1	DAS	Power Supply, H-P 6627A	-	3452A01975	Yes	
2	DAS	Power Supply, H-P 6627A	-	3452A01956	Yes	
3	DAS	Data Acquisition/Control Unit H-P 3497A	-	2936A245539	No	-
4	DAS	Digital Multimeter H-P 3458A	-	2823A15047	Yes	
5	EM	Vacuum Gauge Controller Granville-Phillips Model 316	EG-1a, -1b	2827	No	-
6	EM	Vacuum Gauge Controller Granville-Phillips Model 316	AG-2a, -2b	2826	No	-
7	EM	Vacuum Gauge Controller Granville-Phillips Model 316	EG-3	2828	No	-
8	EM	MKS PDR-C-2C	EG-2, FCG	92022108A	No	-
9	EM	Flow meter – Matheson 8170	EFM-1	96186	No	-
10	EM	Flow meter totalizer Matheson 8124	EFM-1	96174	No	-
11	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Main Tank	96-409-11	No	-
12	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Guard Tank	96-409-10	No	-
13	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Well	96-409-9	No	-
14	EM	Liquid Helium Level Controller American Magnetics, Inc. 136	LLS Axial Lock	96-409-12	No	-
15	EM	Pressure Controller – MKS 152F-92	EV-7a, -7b	96203410A	No	-
16	EM	Power Supply HP 6038A	H08D Tank Heater	96023407A	Yes	
17	EM	Power Supply	H09D Tank	3511A-13332	Yes	

No.	Location	Description	User Name	Serial No.	Cal Required	Status Cal due date
		HP 6038A	Heater			
18	EM	Power Supply HP 6038A	RAV Power Supply	3329A-12486	Yes	
19	EM	Vac Ion Pump power supply Varian 929-0910, Minivac	SIP	5004N	No	-
20	EM	Flow meter totalizer Veeder-Root	PFM-1	576013-716	No	-
21	GM	Pressure Gauge, Heise	AG-1	CC-122077	No	-
22	GM	Pressure Gauge, Marshall Town	AG-3	N/A	No	-
23	GM	Main Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller	-	C-19950	No	-
24	GM	Guard Tank Heat Exchanger: a) Thermocouple, b) Current meter, c) Temperature set point controller	-	C-09920	No	-
25	VM	Vacuum Gauge readout, Granville-Phillips 316	VG-3 VG-4	2878	No	-
26	VM	Vacuum Gauge readout, Granville-Phillips 360	VG-1, VG-2 VG-5	96021521	No	-

#### E.5. Configuration Requirements

##### E.5.1. Main Tank

Liquid in the Main Tank must be at its normal boiling point (NBP)

##### E.5.2. Guard Tank

The Guard Tank may contain liquid or be depleted.

##### E.5.3. Well

The Well must be evacuated.

##### E.5.4. SMD Vacuum Shell

The Vacuum Shell pressure must be less than  $5 \times 10^{-5}$  torr. Document No. P1015, *Connect Vacuum Module to SMD*, contains the procedure for connecting to and pumping on the SMD vacuum shell.

##### E.5.5. Alarm System

1. The DAS alarm system must be enabled and contain the following alarm set-points:
  - a. Top of lead bag temperature set (CN 175 and CN 178) at  $T \leq 6.0$  K.
  - b. Relative Guard Tank Pressure (CN 46) set at  $P \geq 0.3$  torr.

##### E.5.6. GSE and Non-flight Hardware

1. The ion-pump magnet is installed.
2. The Fill Cap Assembly must be installed at SV-13 (See Figure 3)
3. Dewar Adapter heaters on SMD must be installed and operational.

#### E.6. Optional Non-flight Configurations

The following modifications or non-flight arrangement of the basic SMD configuration may also be in place. They are incidental to the performance of this procedure and not required.

1. The SMV may be installed in its transportation and test fixture.
2. The Vacuum shell pump out port at SV-14 may be connected to the Vacuum Module (P/N 5833816) via a 2-in valve and pumping line, with the valve in either the closed position or in the open position. The Vacuum Module pump may be; off, actively pumping the pumping line up to a closed SV-6, or actively pumping the vacuum shell.

**F. REFERENCE DOCUMENTS****F.1. Drawings**

<b><i>Drawing No.</i></b>	<b><i>Title</i></b>
LMMS-5833394	Instrumentation Installation

**F.2. Supporting documentation**

<b><i>Document No.</i></b>	<b><i>Title</i></b>
LMMC-5835031	GP-B Magnetic Control Plan
GPB-100153C	SMD Safety Compliance Assessment
LM/P 479945	Missile System Prelaunch Safety Package
SU/GP-B P0141	FIST Emergency Procedures
LMSC-P088357	Science Mission Dewar Critical Design Review
SU/GP-B P0108	Quality Plan
LMMS GPB-100333	Science Mission Dewar Failure Effects and Causes Analysis
SU/GP-B P059	GP-B Contamination Control Plan
EM SYS229	Accident/Mishap/Incident Notification Process
EWR 127-1	Eastern and Western Range Safety Requirements
KHB 1710.2 rev E	Kennedy Space Center Safety Handbook

**F.3. Additional Procedures**

<b><i>Document No.</i></b>	<b><i>Title</i></b>
SU/GP-B P0879	Accident/Incident/Mishap Notification Process
SU/GP-B P1015	Connect Vacuum Module to SMD
SU/GP-B P0875	GP-B Maintenance and Testing at all Facilities

Operation Number: \_\_\_\_\_

Date Initiated: \_\_\_\_\_

Time Initiated: \_\_\_\_\_

**G. OPERATIONS**

**G.1. Pre Operations Verifications**

- o Verify SU QA notified.  
Record: Individual notified \_\_\_\_\_,  
Date/time \_\_\_\_/\_\_\_\_.
- o Verify NASA program representative notified.  
Record: Individual notified \_\_\_\_\_,
- o Record calibration due dates in Table 1 and section E.3.6.
- o Verify that persons actually performing this procedure have initialed their names in Sec. D.3 and the name of the Test Director is circled.
- o Complete pre-operations review.
- o Verify LM personnel prepared to open RAV-2 when necessary
- o Verify proper operation of GP-B Cryogenic Team oxygen monitor
- o Verify availability and functioning of an emergency shower.

QA Witness: \_\_\_\_\_

**G.2. Verify Purity of All Sources of Helium Supply**

G.2.1. Record serial number on helium bottle/s.

- 1. \_\_\_\_\_ 2. \_\_\_\_\_ 3. \_\_\_\_\_
- 4. \_\_\_\_\_ 5. \_\_\_\_\_ 6. \_\_\_\_\_

Verify helium bottle/s have been tested for purity and record Op. Number.

Op. Number: \_\_\_\_\_

Record Step Number: \_\_\_\_\_

QA Witness: \_\_\_\_\_

**G.3. Verify Configuration Requirements**

G.3.1. Ensure Dewar Adapter heaters are operational and record:

G.3.2. Ensure ion-pump magnet installed.

- G.3.3. Ensure Vacuum Shell Pressure  $< 5 \times 10^{-5}$  torr.
1. Turn on Vac-ion pump and record time of day \_\_\_\_\_
  2. Use DAS [Monitor Data] for CN 99.
  3. When value is steady, record pressure (IP) \_\_\_\_\_ torr.
  4. If pressure is above  $5 \times 10^{-5}$  torr, turn off Vac-ion pump and perform procedure P1015 to pump out SMD vacuum shell with Vacuum Module. Record operation number \_\_\_\_\_.
  5. Exit [Monitor Data] and collect data with [Set Data Interval] to 5 min.
  6. When data cycle is complete, turn off Vac-ion pump.

**CAUTION**

**This procedure necessitates closure of the Main Tank vent. During the period of closure the temperatures at the top of the lead bag are to be continuously monitored. Ensure that these temperatures are on the DAS alarm list and appropriately alarmed. Failure to comply may result in equipment damage.**

- G.3.4. Ensure DAS alarm system enabled and record set points.
1. **Top of lead bag temperature** – ensure CN [175] on DAS alarm list and set to alarm at  $T \leq 6.0$  K.  
Record set point. \_\_\_\_\_ K
  2. **Top of lead bag temperature** – ensure CN [178] on DAS alarm list and set to alarm at  $T \leq 6.0$  K.  
Record set point. \_\_\_\_\_ K
  3. **Relative Guard Tank pressure** – ensure CN [46] on DAS alarm list and set to alarm at  $\Delta P \geq 0.3$  torr.  
Record set point. \_\_\_\_\_ torr
- G.3.5. Ensure liquid-level alarms enabled and record set points.
1. **Main Tank** – ensure liquid-level alarm set  $\geq 20\%$ .  
Record set point. \_\_\_\_\_ %
  2. **Guard Tank** – ensure liquid-level alarm set  $\geq 10\%$ .  
Record set point. \_\_\_\_\_ %
- G.3.6. Ensure Main Tank Vent Cap installed. If not, perform procedure P1007, *Disconnect Main Tank Vent Line From Gas Module – Main Tank at NBP*, and record operation number \_\_\_\_\_.
- G.3.7. Ensure Guard Tank Vent Cap installed. If not, perform procedure P1009, *Disconnect of Guard Tank Vent Line From Gas Module*, and record operation number \_\_\_\_\_.
- G.3.8. Ensure Fill Cap Assembly installed at SV-13.

QA Witness: \_\_\_\_\_

**G.4. Verify SMD in Standard Configuration**

G.4.1. Using the RAV log book verify that the dewar's internal valves are in the following positions. If not, investigate to ensure previous RAV operations properly recorded. If necessary, note resolution in D-log.

1. **Open:**RAV-3, and RAV-6B.
2. **Closed:**RAV-1, RAV-2, RAV-5, RAV-6A, and RAV-7.

G.4.2. Verify that SMD external valves are in the following positions.

1. **Open:**SV-9.
2. **Closed:**SV-13, STV and FCV.

QA Witness: \_\_\_\_\_

**G.5. Establish Vent Line Configuration and Record Initial Conditions**

G.5.1. Record pressures, relative to atmospheric

1. Guard Tank pressure (GTV-G, CN [46]) \_\_\_\_\_ torr.
2. Main Tank pressure (STG, CN [49]) \_\_\_\_\_ torr .

G.5.2. Establish Guard Tank vent configuration:

- 
- o Liquid in Guard Tank
    1. Verify GTV-V open
    2. Verify GTV-Va closed
- 
- o Guard Tank depleted with pressure independently regulated at GTV-Va.
    1. Verify GTV-Va open and connected to APR-2V
    2. Verify APR-2 set to 2 psig
    3. Verify EV-23 closed
- 

G.5.3. Record liquid helium levels:

1. Main Tank level (LL-1D or LL-2D) \_\_\_\_\_%
2. Guard Tank Level (LL-5D or LL-6D) \_\_\_\_\_%

QA Witness: \_\_\_\_\_

**G.6. Check Initial pressure in Fill Line**

G.6.1. Turn on pump AP-1

G.6.2. Install a pumping line between valve FCV on the Fill Cap Assembly and the Access Port #1 of the Auxiliary gas section.

G.6.3. Open AV-8.



- G.6.4. Open AV-3.
- G.6.5. Open valve FCV and evacuate to 20 mtorr as measured at AG-2.
- G.6.6. Close AV-8 and FCV.
- G.6.7. Once the pressure in the Fill Cap Assembly (PFCG) has stabilized, record Fill Cap Assembly pressure (PFCG): \_\_\_\_\_ torr.
- G.6.8. Open valve SV-13 and bring the Fill Cap Assembly up to the pressure in the SMD fill line and record fill line pressure (PFCG): \_\_\_\_\_ torr.

QA Witness: \_\_\_\_\_

G.7. **Set up Data Acquisition**

- G.7.1. Set Main Tank sampling interval to 1 minute.
- G.7.2. Set Guard Tank sampling interval to 1 minutes.

**Note:**

Refer to Operating Instructions for mechanics of DAS keyboard/mouse operations.

- G.7.3. Set DAS data cycle time to 5 minutes or less: use [Set D.C. Interval].
- G.7.4. Set up special data collection

QA Witness: \_\_\_\_\_

**CAUTION**

**When RAV-1 is closed, the temperature of the Lead Bag and the Main Tank pressure may increase quickly. The test director should monitor the special data continuously. In addition, RAV-2 should be opened as soon as the pressure differential between the Main Tank and the Guard Tank is sufficient to transfer liquid. Failure to comply may result in equipment damage.**

G.8. **Raise Pressure in Fill Line by opening RAV-1 and close SV-9**

- G.8.1. Ensure LM personnel on standby and ready to open RAV-2
- G.8.2. Close SV-9
- G.8.3. Enter comment in DAS, "Closed Main Tank Vent Valve- SV-9"
- G.8.4. **Ensure all** RAV controller selection switches in OFF position.
- G.8.5. Turn on RAV power supply and adjust current limit to 1.85 amps.
- G.8.6. Adjust power supply to 28 VDC.
- G.8.7. Power up controller #1.
- G.8.8. Position controller #1 selection switch to RAV-1.
- G.8.9. Record initial switch status: Open: 0 0 Closed: 0 0

G.8.10. Activate controller #1 to open RAV-1 and record:

1. Run time: \_\_\_\_\_ seconds
2. Current draw: \_\_\_\_\_ amp
3. Time of day: \_\_\_\_\_

G.8.11. Record final switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$

G.8.12. When convenient, record operation in RAV log book.

G.8.13.

**NOTE:**

Do not power off RAV controller.

G.8.14. Verify that the Fill Cap Assembly pressure (PFCG) rises to pressure > 760 torr.

Record fill line pressure (PFCG): \_\_\_\_\_ torr.

QA Witness: \_\_\_\_\_

**G.9. Prepare to Transfer**

G.9.1. Prepare to open RAV-2

G.9.2. Request LM personnel install arming plug for RAV-2

G.9.3. Request LM SV Operations open RAV-2.

G.9.4. Verify RAV-2 is open by observing initial increase flow at EFM-3 and then decay and a decrease in pressure at FCG.

G.9.5. Record FCG \_\_\_\_\_ torr, GTV-G \_\_\_\_\_ torr

G.9.6. Open GTVC-Fill Vent valve to reduce pressure in Guard Tank and record time: \_\_\_\_\_.

G.9.7. When Guard Tank pressure stabilizes, record pressure relative to atmospheric, GTV-G \_\_\_\_\_ torr.

G.9.8. Record relative MT pressure desired for sustaining transfer \_\_\_\_\_ torr.

**Note:**

There is sufficient pressure differential to transfer when the Main Tank pressure is 30 torr greater than Guard Tank pressure GTV-G.

G.9.9. Record desired final Guard Tank level: \_\_\_\_\_ %.

G.9.10. Input comment to DAS "Start Internal transfer to Guard Tank".

QA Witness: \_\_\_\_\_

**G.10. Initiate Transfer**

G.10.1. Turn on Tank Heater (H-8D or H-9D) power supply and adjust current limit to 1.25 amps.



2. Record GTVC-G \_\_\_\_\_ torr

3. When convenient, record operation in RAV log book.

G.11.7. Record Guard Tank Pressure (GTVC-G/GTV-G): \_\_\_\_\_ torr (relative to atm.).

G.11.8. Record Main Tank pressure (STG): \_\_\_\_\_ torr (relative to atm.).

G.11.9. Close GTVC Fill Vent valve.

G.11.10. Open SV-9

G.11.11. Once conditions have stabilized, record final transfer conditions:

1. Main Tank level (LL-1D or LL-2D) \_\_\_\_\_ %

2. Guard Tank Level (LL-5D or LL-6D) \_\_\_\_\_ %

QA Witness: \_\_\_\_\_

**G.12. Condition Dewar Fill Line and Fill Cap Assembly.**

G.12.1. Ensure pumping line installed between Fill Cap Assembly at valve FCV and Auxiliary Gas Section access port no. 1.

G.12.2. Ensure FCV closed.

G.12.3. Close/verify closed AV-1 and AV-9.

G.12.4. Ensure pump AP-1 on.

G.12.5. Open AV-8 and AV-3 and evacuate pumping line to <25 mtorr measured at AG-2b.

G.12.6. Close RAV-1 as follows :

**Note:**

Relief of the Dewar fill line will be through the relief valve in the Fill Cap Assembly until the next operation.

1. Verify controller #1 already powered up and controller #1 selection switch set to RAV-1. If not, perform the following steps:

- a. Ensure controller #1 selection switch in off position
- b. Power up controller #1.
- c. Position controller #1 selection switch to RAV-1.

2. Record initial switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$

3. Activate controller #1 to close RAV-1 and record:

- a. Run time: \_\_\_\_\_ seconds
- b. Current draw: \_\_\_\_\_ amp
- c. Time of day: \_\_\_\_\_

4. Record final switch status: Open:  $\theta$   $\theta$  Closed:  $\theta$   $\theta$

5. Turn controller #1 selection switch to OFF.

6. Power off controller #1.

- 7. Turn off RAV power supply.
- 8. When convenient, record operation in log book.

G.12.7. Open FCV and evacuate Dewar fill line to < 25 mtorr as measured at AG-2b, and record AG-2b: \_\_\_\_\_ torr

G.12.8. Close SV-13 and torque to 60 +/- 5 in-lbs.

QUALITY\_\_\_\_\_

G.12.9. Close AV-8.

G.12.10. Open AV-1.

G.12.11. Open AV-9 until pressure reaches 1.5 psig at AG-1, then close AV-9.

G.12.12. Close AV-1 and AV-3.

G.12.13. Close FCV.

G.12.14. Turn off pump AP-1.

G.12.15. Remove pumping line from Fill Cap Assembly.

G.12.16. Install KF-25 blank-off cap on valve FCV and record:

1. PFCG pressure: \_\_\_\_\_

2. Time of day: \_\_\_\_\_

G.12.17. Verify closure of SV-13 by observing the pressure in the Fill Cap Assembly (PFCG) until satisfied that no gas is leaking into the Dewar Fill line. After 30 minutes record:

Time of day:\_\_\_\_\_

PFCG pressure:\_\_\_\_\_

**Note:**

If PFCG drops by more than 0.5 torr in 30 minutes, retorque SV-13 and repeat steps G.11.8 through G.11.16.

QA Witness:\_\_\_\_\_

**G.13. Configure the DAS and Liquid Level Sensors**

G.13.1. Input comment to DAS “End of Internal transfer to Guard Tank”.

G.13.2. Set the DAS data cycle to 15 minutes.

G.13.3. Set all the liquid level sampling intervals to 10 minutes.

G.13.4. Ensure DAS alarm enabled and record set points if changed

- o Thermal conditions substantially unchanged, alarm set points for the lead bag unchanged
- o Thermal conditions substantially changed, temperature alarm points reset as follows:

-

- a. Top of Lead Bag set point \_\_\_\_\_ K ( $\leq 6.0$  K)  
[CN 29]
- b. Top of Lead Bag set point \_\_\_\_\_ K ( $\leq 6.0$  K)  
[CN 28]

G.13.5. Ensure liquid level sensor alarms enabled and record set points if changed.

- 1. Main Tank Level                      Set Point \_\_\_\_\_%
- 2. Guard Tank Level                    Set Point \_\_\_\_\_%

**CAUTION**

**Monitor and maintain positive pressure in the Guard Tank. The Guard Tank may tend to subcool following the completion of this procedure. Ensure Guard Tank pressure on DAS alarm list. Failure to comply may result in equipment damage.**

G.13.6. Ensure Guard Tank pressure on DAS alarm list and set to alarm at  $> 0.3$  torr differential.

QA Witness: \_\_\_\_\_

**G.14. Verify Final Configuration**

G.14.1. Ensure GTVC-V closed

G.14.2. Ensure SV-9 open

G.14.3. Ensure all EV valves closed.

G.14.4. Ensure all AV valves closed

G.14.5. Ensure that all liquid level sensors are set at a sampling rate of 10 minutes.

G.14.6. Ensure that power to Vac-Ion pump is off.

G.14.7. Ensure all RAV operations(open and close) recorded in log book

1. RAV-1

2. RAV-2

G.14.8. Record Main Tank liquid usage:

1. Start level: \_\_\_\_\_ %, Finish level : \_\_\_\_\_%.

2. Amount transferred: \_\_\_\_\_ liters ( use 1 % = 24 l)

G.14.9. Verify completion of post operations checklist

**H. PROCEDURE SIGN OFF**

**Completed by:** \_\_\_\_\_

**Witnessed by:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Time:** \_\_\_\_\_

**Quality Manager** \_\_\_\_\_ **Date** \_\_\_\_\_

**Payload Test Director** \_\_\_\_\_ **Date** \_\_\_\_\_




Figure 1: Gas Module








Figure 3: MT Vent Cap, GTVA GT Vent Cap



**APPENDIX 1**

DATE	CHECKLIST ITEM	COMPLETED	REMARKS
	1. Verify the test procedure being used is the latest revision.		
	2. Verify all critical items in the test are identified and discussed with the test team.		
	3. Verify all required materials and tools are available in the test area.		
	4. Verify all hazardous materials involved in the test are identified to the test team.		
	5. Verify all hazardous steps to be performed are identified to the test team.		
	6. Verify each team member is certified for the task being performed and knows their responsibilities..		
	7. Confirm that each test team member clearly understands that he/she has the authority to stop the test if an item in the procedure is not clear.		
	8. Confirm that each test team member clearly understands that he/she must stop the test if there is any anomaly or suspected anomaly.		
	9. Notify management of all discrepancy reports or d-log items identified during procedure performance. In the event an incident or major discrepancy occurs during procedure performance management will be notified immediately.		
	10. Verify/perform pre task engineering/safety high-bay walk down. Verify noted discrepancies have been corrected.		
	11. Confirm that each test team member understands that there will be a post-test team meeting.		
	Team Lead Signature: _____		

-

J. **APPENDIX 2**

DATE	CHECKLIST ITEM	COMPLETED	REMARKS
	1. Verify all steps in the procedure were successfully completed.		
	2. Verify all anomalies discovered during testing are properly documented.		
	3. Ensure management has been notified of all major or minor discrepancies.		
	4. Ensure that all steps that were not required to be performed are properly identified.		
	5. If applicable sign-off test completion.		
	6. Verify all RAV valve operations have been entered in log book		
	7. Verify the as-run copy of procedure has been filed in the appropriate binder		
	Team Lead Signature: _____		

K. **APPENDIX 3– CONTINGENCY RESPONSES**

	Condition	Circumstance	Response
1	Temperature limits (CN 1 or 28) exceeded	Main tank is not venting	<p>ALLOW MAIN TANK TO VENT</p> <p>If SV-9 is closed:</p> <p><b>Close EV-17 (if open) and verify EV-9 open, crack open SV-9 to allow MT to vent. Adjust SV-9 as necessary to restore temperature(s) below alarm limits. Open EV-6 and EV-18 if higher flow rate is needed.</b></p> <p>If SV-9 open and EV-9 closed:</p> <p><b>Open EV-9 for short periods (~15 sec) and allow increased flow from Main tank; in addition, Open EV-6 and EV-18 if higher flow rate is needed.</b></p> <p>If SV-9 and EV-9 open</p> <p><b>Open EV-6 and EV-18 for higher flow</b></p> <p><b>If problem persists see item 3</b></p>
2		Main tank is venting	<p>PROMOTE INCREASE IN MAIN TANK VENTING</p> <p>Power up heater at H08D or H0-9D and starting at 15 vdc input increase power until increased flow has cooled the problem area</p>
3	Burst disk rupture (MT/GT)	Anytime	Evacuate room
4	Oxygen Monitor Alarm	Anytime	Evacuate room
5	Liquid Nitrogen Spill	Anytime	Clear area until all spilled liquid has evaporated.